

4 March 2022

ASX ANNOUNCEMENT

DFS UPDATE AND HIGH GRADE ORE SWEEPED FROM NEW HISTORICAL MINES

- **High-Grade assay-**
 - Beverly Hills sweepings grabs – 15.79g/t Au and 4.37g/t Au
 - Beverly Hills chip samples – 11.79g/t Au
 - Desire sweepings grabs – 14.27g/t Au and 10.79g/t Au
- **Feasibility study 80% completion:**
 - Metallurgical testwork nearing completion
 - Mine Designs
 - Geotechnical investigation
 - Underground investigations
- **Plant demolition in progress in preparation for new plant construction**
- **Environmental Scoping Report submitted for MR83**



TGME Plant at 70% demolition


(Note Gold Room, Elution Circuit, Mill, 3 Pre-conditioning tanks, all existing stores, and administration building will not be demolished)

Theta Gold Mines Limited (“Theta Gold” or “Company”) (ASX: TGM, TGMO | OTCQB: TGMGF) is pleased to announce the progress made with its underground gold project Feasibility study (“FS”), environmental approvals, and preparation for plant construction. The Beta, Frankfort, CDM, and Rietfontein mines are collectively referred to as TGME Underground (UG) Project.

Discoveries made recently, namely Beverly Hills and Desire mines, form part of the 43 historical mines under management. Both have experienced very little modern exploration. We now know through underground plans and mine surveys, Desire is one of the larger underground mining complexes in the Goldfield with historic underground workings extending kilometers.

The Desire Mine complex is 1.5km on strike and 3.2km on dip, making this one of the largest unexplored old mines under management. The Desire Mine complex exploited the Portuguese Reef, producing approximately 170Koz Au from 563Kt, grading 9.41 g/t Au. The mine area overlaps parts of the farms Graskop 564KT, Desire 563KT (10167 MR), Ponieskrans 543KT (83 MR), and Grootfontein 562KT (341 MR).

Desire Mine Locality and Met sample



Locality Plan of Desire Mine Workings

Theta's Chairman Bill Guy commented: *"The results of the grab samples taken at both Desire and Beverly Hills Mines are very encouraging as the results indicate high grades within these Mines. The Beverly Hills Mine is currently planned and scheduled as part of the Frankfort Mines LoM.*

The Desire Mine host a large flat reef system, the results of the high grade grab samples are consistent with historical mine evaluation plans. The Desire Mine will undergo further sampling and test work as part of the continuous exploration of the 43 Historical Mines under management.

The permanent onsite team will continue with sampling and exploration work. The team is on track to complete the DFS in Q2 2022. The geotechnical investigations were conducted according to plan with encouraging results. Metallurgical test work continued with bulk samples (approx. 1.5 tons per Mine) taken from , Rietfontein and CDM Mines. These samples are currently at the Laboratory.

The team has completed the final permitting scoping phase for Mining Right 83. The final scoping report will now be assessed by the DMRE and once approved the process will move to the Environmental Impact Assessment (EIA) phase of the permitting process.

Summary

1. Feasibility study progress

1.1. Metallurgical test work nearing completion

The underground gold project Definitive Feasibility Study ("DFS") that started in September 2021 is progressing well, currently at 65% completion with final completion expected in Q2 2022. In support of the FS, metallurgical test work, mine designs, geotechnical studies, and underground investigations are now nearing completion.

In addition to the metallurgical test work undertaken for the Preliminary Feasibility Study ("PFS"), a further bulk sample was taken from Frankfort Mine by trenching the reef accumulation generated by the trial mining, providing a representative sample in terms of ore variability and particle size distribution. The PFS study included a single rougher flotation stage and indicated limited sensitivity to grind. It was decided to conduct additional flotation test work confirming the plant process flow. The flotation trials are complete and largely support the PFS results. The carbon and sulphide flotation products are currently submitted for analysis, which will allow for final circuit mass balancing and financial modeling. These results are expected in the first week of March 2022.



Carbon flotation indicating high flotation kinetics

The sulphide flotation kinetics are extremely rapid indicative of a largely sulphide orebody




1.2. Mine Designs

The overall mine designs are progressing well with the ventilation studies for Beta, CDM and Frankfort completed following the mine design and mining schedules. The surface infrastructure of the mining operations is in the process of being aligned and adjusted to recommended environmental layouts. The optimisation of the mining power requirements has been completed and, informing the bulk power supply infrastructure design.

1.3. Geotechnical investigation

A comprehensive gravity survey was conducted by Applied Scientific Services and Technologies at Frankfort, Beta and CDM mines, and at the central Tailings Storage Facility (TSF). The gravity surveys were carried out, generally, on a 10 meters grid. Thirty-three percussion boreholes were drilled, in accordance with SANS 1936-2 standards. The boreholes were drilled to a depth of 60 meters, with chip samples taken at 1-meter intervals and logged in accordance with the standard procedure proposed by Brink and Bruin. The results of the geotechnical investigation will be submitted to the Council of Geoscience for comments and recommendations for inclusion in final TSF and surface infrastructure designs.



Boreholes drilled at TSF and Beta Mine

1.4. Underground investigations


Underground expeditions are continuously conducted by the mining team into the four mines that form part of the phase 1 project, as well as other mines that will be included in subsequent phases of development. Multiple access points via existing adits are therefore investigated to determine safe accessibility, and where old reef development and stoping areas are accessed, the areas are made safe and sampled for grade verification, metallurgical testwork and rock engineering assessments.

Most of these workings haven't been actively mined since the pre-world-war periods, while a few were last mined around 2008. Most of the stope panels are still accessible due to the excellent ground conditions and support provided by stone packing, and more recent timber support. Several haulages, reef drives, and stope panels are found to still contain large amounts of broken ore, which provide opportunities to complement primary mining tons with cheap, immediately available ore that can be fed to the plant upon commissioning.

Apart from the continuous verification of favourable mining conditions, another positive outcome of investigations is that only limited flooding of the old mines took place. This is due

to the multiple access points and flat nature of the reef, resulting in limited water accumulation. Access ways will be rehabilitated and re-equipped before mining will commence.

Note: Historical plans can be referenced and orientated from surface openings and internal markers still present in the old mines.



Historical Plans mapping out routes during underground investigations




Top Rho reef band



Bottom Rho reef band

The Rho Reef is one of over 40 historically exploited reef systems in the Goldfield. Historic Rho Reef production was 670koz Au from 2.7mt at a head grade of 7.70 g/t Au. Originally correlated with the Lower Theta Reefs on Theta Hill, the Rho Reef is now known to locate stratigraphically higher and commonly manifests as two bedding parallel reefs with an approximate 3m parting. Historic mining stretches over a distance of 4 km northwards covering the Peach Tree Creek, Dukes Hill, Clewer, and Morgenzon workings. A largely unexplored 7km strike exploration area of interest exists north from Morgenzon to the Frankfort workings (see below).



Rho Reef exploration area of interest north from Morgenzon to Frankfort Mine

2. Plant demolition in progress in preparation for new plant construction

As part of the preparation for the installation of the first phase new gold plant, TGME has appointed the services of Jet Demolition to remove the redundant plant equipment. The process started in the 2nd week of January 2022. Specialized equipment is utilized for demolition, after which it is reduced in size and made ready for transport to scrap merchants. The project is now complete.



Plant prior to demolition




Plant at 70% demolition

3. Sampling of old Mines


As part of TGM's exploration strategy ore samples are being taken at prioritised old mines. Initial samples taken at Beta South Mine, have been delivered to Gold 1 laboratories for analysis with results expected towards the end of February 2022. Grab samples taken at Beverly Hills and Desire mine were from old broken ore (sweepings) left in the stope panels. Random samples are taken from this broken ore where safe entry permits into the old stope panels. Samples are collected at the top, middle, and bottom of the stope panel. These samples are then delivered to Gold 1 or SGS laboratories for evaluation. The more chip channel samples at Frankfort Beverly Hills Mine are taken on a 12-meter grid spacing, channels cut into the rock from top hangingwall contact to bottom footwall contact. The 25cm between the two parallel cuts is chipped out, bagged, and transported to the laboratories. Preliminary assay results are shown below. Further sampling inclusive of bench scale amenability to gravity and flotation concentration is in progress.

- Beverly Hills sweeping grab samples – 15.79 g/t Au and 4.37g/t Au (WGS84 UTM 271354E; 7255302 S)
- Beverly Hills chip samples – 11.79g/t Au
- Desire sweeping grab samples – 14.27g/t Au and 10.79g/t Au (WGS84 UTM 276162E; 7240496 S)



Frankfort Bevetts Reef Au g/t and locality of Berverly Hills MET Testwork Sample

Desire Mine Locality and Met sample



Desire Mine locality and site of metallurgical sample

4. Environmental Scoping Report submitted

The final scoping report for the environmental authorisation permitting process for the 83 MR underground project was submitted to the Department of Mineral Resources and Energy (DMRE) on 3 February 2022.



Final scoping report delivered to the DMRE on 3 February 2022

Various stakeholder meetings took place before the submission of the final scoping report as part of the required public participation process. A very successful open day was held in Pilgrims Rest on 15 January 2022 with a good turnout of almost 70 people from the community and various interested parties. Feedback from the open day was very positive and the community is excited about the job opportunities and economic upliftment that will be created by the project. Overall the sentiment was positive towards the proposed project. With the significant turnout at the open day, adding to numerous other consultation meetings that were held with interested and affected parties, the procedural requirement to consult widely during the scoping phase has been satisfied.



Open day consultation meeting held on 15 January 2022

The final scoping report will now be assessed by the DMRE and once approved the process will move to the Environmental Impact Assessment (EIA) phase of the project.

This announcement was authorised for release by Mr Bill Guy, Chairman.

For more information please visit www.thetagoldmines.com or contact:

Bill Guy, Chairman

Theta Gold Mines Limited

T: + 61 2 8046 7584 E: billg@thetagoldmines.com

Webpage: www.thetagoldmines.com



<https://twitter.com/ThetaGoldMines>



<https://www.linkedin.com/company/thetagoldmines/>

COMPETENT PERSONS STATEMENT

Exploration Results

The information in this press release relating to Exploration results is based on, and fairly reflects, the information and supporting documentation compiled by Mr Phil Bentley (MSc (Geol); MSc (Minex), Pr. Sci.Nat No 400208/05, FGSSA) a consultant to the Company and a member of the South African Council for Natural Scientific Professions.

ABOUT THETA GOLD MINES LIMITED

Theta Gold Mines Limited (ASX: TGM | OTC: TGMGF | FWB: 3LM) is a gold development company that holds a range of prospective gold assets in a world-renowned South African gold mining region. These assets include several surface and near-surface high-grade gold projects which provide cost advantages relative to other gold producers in the region.

Theta Gold's core project is located next to the historical gold mining town of Pilgrim's Rest, in Mpumalanga Province, some 370km northeast of Johannesburg by road or 95km north of Nelspruit (Capital City of Mpumalanga Province). Following small scale production from 2011 – 2015, the Company is currently focussing on the construction of a new gold processing plant within its approved footprint at the TGME plant, and for the processing of the initial ore reserves.

The Company aims to build a solid production platform to over 160kozpa based primarily around shallow, open-pit or adit-entry shallow underground hard rock mining sources. Theta Gold has access to over 43 historical mines and prospect areas that can be accessed and explored, with over 6.7Moz of historical production recorded.

Theta Gold holds 100% issued capital of its South African subsidiary, Theta Gold (SA) Pty Ltd ("TGSA"). TGSA holds a 74% shareholding in both Transvaal Gold Mining Estates Limited ("TGME") and Sabie Mines (Pty) Ltd ("Sabie Mines"). The balance of shareholding is held by Black Economic Empowerment ("BEE") entities as part of the country's ESG initiatives. The BEE shareholding in TGME and Sabie Mines is comprised of a combination of local community trusts, an employee trust and a strategic entrepreneurial partner.



DISCLAIMER

This announcement has been prepared by and issued by Theta Gold Mines Limited to assist in informing interested parties about the Company and should not be considered as an offer or invitation to subscribe for or purchase any securities in the Company or as an inducement to make an offer or invitation with respect to those securities. No agreement to subscribe for securities in the Company will be entered into on the basis of this announcement.


This announcement may contain forward looking statements. Whilst Theta Gold has no reason to believe that any such statements and projections are either false, misleading or incorrect, it does not warrant or guarantee such statements. Nothing contained in this announcement constitutes investment, legal, tax or other advice. This overview of Theta Gold does not purport to be all inclusive or to contain all information which its recipients may require in order to make an informed assessment of the Company's prospects. Before making an investment decision, you should consult your professional adviser, and perform your own analysis prior to making any investment decision. To the maximum extent permitted by law, the Company makes no representation and gives no assurance, guarantee or warranty, express or implied, as to, and take no responsibility and assume no liability for, the authenticity, validity, accuracy, suitability or completeness of, or any errors in or omissions, from any information, statement or opinion contained in this announcement. This announcement contains information, ideas and analysis which are proprietary to Theta Gold.

FORWARD LOOKING AND CAUTIONARY STATEMENTS



This announcement may refer to the intention of Theta Gold regarding estimates or future events which could be considered forward looking statements. Forward looking statements are typically preceded by words such as "Forecast", "Planned", "Expected", "Intends", "Potential", "Conceptual", "Believes", "Anticipates", "Predicted", "Estimated" or similar expressions. Forward looking statements, opinions and estimates included in this announcement are based on assumptions and contingencies which are subject to change without notice, and may be influenced by such factors as funding availability, market-related forces (commodity prices, exchange rates, stock market indices and the like) and political or economic events (including government or community issues, global or systemic events). Forward looking statements are provided as a general reflection of the intention of the Company as at the date of release of the document, however are subject to change without notice, and at any time. Future events are subject to risks and uncertainties, and as such results, performance and achievements may in fact differ from those referred to in this announcement. Mining, by its nature, and related activities including mineral exploration, are subject to a large number of variables and risks, many of which cannot be adequately addressed, or be expected to be assessed, in this document. Work contained within or referenced in this report may contain incorrect statements, errors, miscalculations, omissions and other mistakes. For this reason, any conclusions, inferences, judgments, opinions, recommendations or other interpretations either contained in this announcement, or referencing this announcement, cannot be relied upon. There can be no assurance that future results or events will be consistent with any such opinions, forecasts or estimates. The Company believes it has a reasonable basis for making the forward-looking statements contained in this document, with respect to any production targets, resource statements or financial estimates, however further work to define Mineral Resources or Reserves, technical studies including feasibilities, and related investigations are required prior to commencement of mining. No liability is accepted for any loss, cost or damage suffered or incurred by the reliance on the sufficiency or completeness of the information, opinions or beliefs contained in this announcement.

The Feasibility Study referred to in this announcement is based on technical and economic assessments to support the estimation of Ore Reserves. There is no assurance that the intended development referred to will proceed as described, and will rely on access to future funding to implement. Theta Gold Mines believes it has reasonable grounds the results of the Feasibility Study. At this stage there is no guarantee that funding will be available, and investors are to be aware of any potential dilution of existing issued capital. The production targets and forward-looking statements referred to are based on information available to the Company at the time of release, and should not be solely relied upon by investors when making investment decisions. Theta Gold cautions that mining and exploration are high risk, and subject to change based on new information or interpretation, commodity prices or foreign exchange rates. Actual results may differ materially from the results or production targets contained in this release. Further evaluation is required prior to a decision to conduct mining being made. The estimated Mineral Resources quoted in this release have been prepared by Competent Persons as required under the JORC Code (2012). Material assumptions and other important information are contained in this release.

Appendix A Northern Tenement Map



APPENDIX B
Phase 1 UG Project Mine Plans



APPENDIX C

JORC Checklist – Table 1 Assessment and Reporting Criteria

SECTION 1: SAMPLING TECHNIQUES AND DATA																																																																						
Criteria	Explanation	Detail																																																																				
Sampling techniques	Nature and quality of sampling (e.g. cut channels, random chips, or specific specialised industry standard measurement tools appropriate to the minerals under investigation, such as down hole gamma sondes, or handheld XRF instruments, etc.). These examples should not be taken as limiting the broad meaning of sampling.	<p>Sampling types discussed in this section mainly pertain to historical data with the exception of the Theta Project subsequent to the 2017-2019 drilling campaign. Drilling data sampling types include diamond, reverse circulation ("RC"), percussion and auger drilling. Other sampling data types include underground channel chip sampling (as individual sample section composite data points on plans or as development or stope face composite stretch values), grab sampling as well as trench and sample pit sampling for bulk sampling for the purposes of size fraction analysis.</p> <p>The table below outlines the types of sampling data collected or utilised in the Mineral Resource or Exploration Target estimates for each of the Project Areas.</p> <table border="1"> <thead> <tr> <th>Project Area</th><th>Reef</th><th>Sampling Data Types</th></tr> </thead> <tbody> <tr> <td rowspan="2">Rietfontein</td><td rowspan="2">Rietfontein</td><td>Drillhole Data</td></tr> <tr> <td>Channel Chip Sample Data</td></tr> <tr> <td rowspan="2">Beta</td><td rowspan="2">Beta</td><td>Drillhole Data</td></tr> <tr> <td>Channel Chip Sample Data</td></tr> <tr> <td rowspan="2">Frankfort</td><td rowspan="2">Bevetts and Theta</td><td>Drillhole Data</td></tr> <tr> <td>Channel Chip Sample Data</td></tr> <tr> <td rowspan="2">Clewer, Dukes Hill & Morgenzon</td><td rowspan="2">Rho</td><td>Drillhole Data</td></tr> <tr> <td>Channel Chip Sample Data</td></tr> <tr> <td rowspan="2">Olifantsgeraamte</td><td rowspan="2">Olifantsgeraamte</td><td>Drillhole Data</td></tr> <tr> <td>Channel Chip Sample Data</td></tr> <tr> <td rowspan="3">Vaalhoek</td><td rowspan="3">Vaalhoek and Thelma Leaders</td><td>Drillhole Data</td></tr> <tr> <td>Channel Chip Sample Data</td></tr> <tr> <td>Stretch Values</td></tr> <tr> <td rowspan="3">Glynn's Lydenburg</td><td rowspan="3">Glynn's</td><td>Drillhole Data</td></tr> <tr> <td>Channel Chip Sample Data</td></tr> <tr> <td>Stretch Values</td></tr> <tr> <td rowspan="2">Theta Project (Theta Hill, Browns Hills and Iota section of Columbia Hill)</td><td rowspan="2">Beta, Shale, Lower Theta, Upper Theta, Lower Rho, Upper Rho and Bevetts</td><td>Drillhole Data</td></tr> <tr> <td>Trench Sampling Data</td></tr> <tr> <td rowspan="2">Columbia Hill (remaining)</td><td rowspan="2">Rho, Shale and Shale Leaders</td><td>Channel Chip Sample Data</td></tr> <tr> <td></td></tr> <tr> <td>Hermansburg</td><td>Eluvial</td><td>RC Drillhole Data</td></tr> <tr> <td>DG1</td><td>Eluvial</td><td>RC Drillhole Data</td></tr> <tr> <td>DG2</td><td>Eluvial</td><td>RC Drillhole Data</td></tr> <tr> <td rowspan="2">DG5</td><td rowspan="2">Eluvial</td><td>Grab Samples</td></tr> <tr> <td>RC Drillhole Data</td></tr> <tr> <td>Glynn's Lydenburg TSF</td><td>Tailings</td><td>Auger Drillhole Data</td></tr> <tr> <td>Blyde TSFs (1, 2, 3, 3a, 4, 5)</td><td>Tailings</td><td>Auger Drillhole Data</td></tr> <tr> <td>TGM Plant</td><td>Tailings</td><td>Auger Drillhole Data</td></tr> <tr> <td rowspan="3">Vaalhoek, South East (DGs), Peach Tree, Ponieskrantz, Dukes Clewer</td><td rowspan="3">Rock Dumps</td><td>Bulk Sampling Data</td></tr> <tr> <td>Trench Sampling Data</td></tr> <tr> <td>Sampling Pit Data</td></tr> </tbody> </table> <p>a) Channel Chip Sampling Data:- Historical (Pre-1946) chip sample values were captured in 'pennyweight' (dwt) units for gold content and in inches for channel width. The quality of the chip samples could not be ascertained due to the historical nature thereof; however, it should be noted chip sampling is a well-established sampling method in the underground South African mining industry. The sampling activity on the mines was usually managed by each mine's survey department and were usually conducted to specific company-wide standards.</p> <p>More recent chip sample values were captured as cm.g/t content values and channel widths were recorded in centimetres as is the case at Frankfort while under ownership of Simmer & Jack Mines Limited. During 2008, Minxcon audited the chip sampling procedure as employed by Simmer & Jack and found the procedures employed to be of industry standard.</p> <p>b) Stretch Values:- In some instances (such as at Vaalhoek and Glynn's Lydenburg) in areas where original sample plans were not available, stretch value plans recording a composite content and channel width</p>	Project Area	Reef	Sampling Data Types	Rietfontein	Rietfontein	Drillhole Data	Channel Chip Sample Data	Beta	Beta	Drillhole Data	Channel Chip Sample Data	Frankfort	Bevetts and Theta	Drillhole Data	Channel Chip Sample Data	Clewer, Dukes Hill & Morgenzon	Rho	Drillhole Data	Channel Chip Sample Data	Olifantsgeraamte	Olifantsgeraamte	Drillhole Data	Channel Chip Sample Data	Vaalhoek	Vaalhoek and Thelma Leaders	Drillhole Data	Channel Chip Sample Data	Stretch Values	Glynn's Lydenburg	Glynn's	Drillhole Data	Channel Chip Sample Data	Stretch Values	Theta Project (Theta Hill, Browns Hills and Iota section of Columbia Hill)	Beta, Shale, Lower Theta, Upper Theta, Lower Rho, Upper Rho and Bevetts	Drillhole Data	Trench Sampling Data	Columbia Hill (remaining)	Rho, Shale and Shale Leaders	Channel Chip Sample Data		Hermansburg	Eluvial	RC Drillhole Data	DG1	Eluvial	RC Drillhole Data	DG2	Eluvial	RC Drillhole Data	DG5	Eluvial	Grab Samples	RC Drillhole Data	Glynn's Lydenburg TSF	Tailings	Auger Drillhole Data	Blyde TSFs (1, 2, 3, 3a, 4, 5)	Tailings	Auger Drillhole Data	TGM Plant	Tailings	Auger Drillhole Data	Vaalhoek, South East (DGs), Peach Tree, Ponieskrantz, Dukes Clewer	Rock Dumps	Bulk Sampling Data	Trench Sampling Data	Sampling Pit Data
Project Area	Reef	Sampling Data Types																																																																				
Rietfontein	Rietfontein	Drillhole Data																																																																				
		Channel Chip Sample Data																																																																				
Beta	Beta	Drillhole Data																																																																				
		Channel Chip Sample Data																																																																				
Frankfort	Bevetts and Theta	Drillhole Data																																																																				
		Channel Chip Sample Data																																																																				
Clewer, Dukes Hill & Morgenzon	Rho	Drillhole Data																																																																				
		Channel Chip Sample Data																																																																				
Olifantsgeraamte	Olifantsgeraamte	Drillhole Data																																																																				
		Channel Chip Sample Data																																																																				
Vaalhoek	Vaalhoek and Thelma Leaders	Drillhole Data																																																																				
		Channel Chip Sample Data																																																																				
		Stretch Values																																																																				
Glynn's Lydenburg	Glynn's	Drillhole Data																																																																				
		Channel Chip Sample Data																																																																				
		Stretch Values																																																																				
Theta Project (Theta Hill, Browns Hills and Iota section of Columbia Hill)	Beta, Shale, Lower Theta, Upper Theta, Lower Rho, Upper Rho and Bevetts	Drillhole Data																																																																				
		Trench Sampling Data																																																																				
Columbia Hill (remaining)	Rho, Shale and Shale Leaders	Channel Chip Sample Data																																																																				
Hermansburg	Eluvial	RC Drillhole Data																																																																				
DG1	Eluvial	RC Drillhole Data																																																																				
DG2	Eluvial	RC Drillhole Data																																																																				
DG5	Eluvial	Grab Samples																																																																				
		RC Drillhole Data																																																																				
Glynn's Lydenburg TSF	Tailings	Auger Drillhole Data																																																																				
Blyde TSFs (1, 2, 3, 3a, 4, 5)	Tailings	Auger Drillhole Data																																																																				
TGM Plant	Tailings	Auger Drillhole Data																																																																				
Vaalhoek, South East (DGs), Peach Tree, Ponieskrantz, Dukes Clewer	Rock Dumps	Bulk Sampling Data																																																																				
		Trench Sampling Data																																																																				
		Sampling Pit Data																																																																				

SECTION 1: SAMPLING TECHNIQUES AND DATA		
Criteria	Explanation	Detail
		<p>value for a stope length or development end were available and included in the database. The integrity of these plans as a source of grade information has been proven in other areas on the same mines where both chip sample plans and stretch value plans were available and were compared. It was found that the correlation to old sampling has been representative of the stretch values in these areas.</p> <p>c) Drillhole Data:- Historical (pre-2007/8) drillhole data (inclusive of diamond, RC, and auger) exists on many of the operations. However very little backing data is available for many of these older holes and it must be assumed that QAQC was not included in the process. Minxcon has however reviewed the general quality of the survey data for these drillholes. For the most part, collar data has been found to agree well with local topography and is considered to be acceptable for modelling purposes.</p> <p>Downhole survey data with respect to diamond and RC drilling is also often absent from the older holes; however, it should be noted that over 98% of these holes were seldom drilled to depths in excess of 150 m and were vertically collared. Only 1.40% of all the drillholes on all the properties were drilled as inclined drillholes, thus it is Minxcon's view that the holes and their relative reef intercept points would be spatially acceptable for modelling purposes.</p> <p>The historical drillhole data has no accompanying assay QAQC, however this fact is considered in allocation of Mineral Resource classification during modelling.</p> <p>More recent drillhole data (inclusive of diamond, RC and auger) from 2008 onward is considered to be of high quality as it was conducted to updated industry standards with the incorporation of drillhole collar survey as well as assay QAQC where blanks and certified reference material were inserted for monitoring purposes, with the inclusion of coarse duplicate samples. These later drilling programmes were also either monitored, audited or managed by Minxcon personnel under Minxcon previous sister company Agere Project Management ("Agere").</p> <p>d) Trench, Sample Pit and Bulk Sampling (Vaalhoek Rock Dump):- In order to evaluate the Vaalhoek Rock Dump, trenches and sample pits were dug. The trenches and pits were surveyed by a Mine Surveyor and were sampled in sections down to a depth 1.2 m, each sample representing a composite of 40 cm down the wall of the trench or pit. These samples were then assayed. The discard material from the trenches and pits was then composited to form a bulk sample of 50 tonnes for conducting size fraction analysis. The nature and quality of the sampling in question has been considered in the Mineral Resource classification for the Vaalhoek Dump, which is Inferred.</p> <p>e) Bulk Sampling (South East (DGs), Peach Tree, Ponieskrantz, Dukes Clewer):- Bulk sampling was done through a triple deck screening plant (bulk samples were between 20t and maximum 520t per waste rock dump).</p> <p>f) Trench Sampling (Theta Project Browns Hill):- Trenching was conducted on Browns Hill during the 2017-2019 drilling campaign to assist in locating the Lower Theta Reef outcrop. Trenches were dug in roughly an east-west orientation to a depth of between 1.0 m to 2.1 m. A total of 10 trenches were dug with an approximate spacing of approximately 30 to 35 m. The trenches were sampled near to vertical at 2 m intervals, due to the very shallow dip of the reef, where full side-wall composite samples were taken. Samples were dispatched to SGS Laboratory in Barberton for analysis. The trench sampling was not used in any evaluation as its only purpose was to locate reef outcrops.</p>
	Include reference to measures taken to ensure sample representivity and the appropriate calibration of any measurement tools or systems used.	<p>a) Chip Sampling:- In concordant reef underground projects chip samples were taken normal to the reef dip and calculated to give a composited value for a true reef thickness. In the case of cross-reefs such as that at Rietfontein, chip sample positions were plotted on the development centre lines indicating face sampling normal to the reef dip. Scatter plots were also generated to examine the data set for errors introduced while capturing the data. All values were converted using factors of 2.54 cm for 1 inch and 1.714285 g/t for 1 dwt.</p> <p>The older underground sampling took place at approximately 6 m spacing along on-reef development, whilst in newer mining areas this spacing was reduced to approximately 2 to 3 m along on-reef development. In the stoping areas a grid was targeted on an approximate 5 m by 5 m grid where applicable, which is a historical grid (Pre-1946). This grid was put in place due to the nugget effect of the reef. The minimum size of the samples was 20 cm to obtain a minimum weight of 500 g.</p> <p>b) Trench, Sample pit and Bulk Sampling (Vaalhoek Rock Dump):- The trenches at Vaalhoek Rock Dump were located and spread as evenly as possible on the top of the dump, while pits were located on the sides of the dump and these were sampled in sections down to a depth 1.2 m, each sample representing a composite of 40 cm down the wall of the trench or pit. The discard material from the trenches and pits was then composited to form a bulk sample of 50 tonnes for conducting size fraction analysis and screened at -10 mm, +40 mm and</p>

SECTION 1: SAMPLING TECHNIQUES AND DATA		
Criteria	Explanation	Detail
		<p>-75 mm. The nature and quality of the sampling in question has been considered in the Mineral Resource classification for the Vaalhoek Dump, which is Inferred.</p> <p>c) Trench, Sample pit and Bulk Sampling (Theta Project):- The trenches were dug in roughly an east-west orientation to a depth of between 1.0 m to 2.1 m. A total of 10 trenches were dug with an approximate spacing of approximately 30 m to 35 m. The trenches were sampled near to vertical at 2 m intervals, due to the very shallow dip of the reef, where full side-wall composite samples were taken. The trench sampling was not used in any evaluation as its only purpose was to locate reef outcrops.</p>
	Aspects of the determination of mineralisation that are Material to the Public Report. In cases where 'industry standard' work has been done this would be relatively simple (e.g. 'reverse circulation drilling was used to obtain 1 m samples from which 3 kg was pulverised to produce a 30 g charge for fire assay'). In other cases more explanation may be required, such as where there is coarse gold that has inherent sampling problems. Unusual commodities or mineralisation types (e.g. submarine nodules) may warrant disclosure of detailed information.	<p>Samples presented in the historical database represent full reef composites for both diamond drilling as well as chip sampling. The historical nature of the data and the high grades encountered implies the use of fire assay as an assay technique. Sample preparation and aspects regarding sample submission for assay are not known due to the historical nature of the sampling data.</p> <p>Underground sampling, for metallurgical purposes, was undertaken at the northern Neck section of Vaalhoek during February, 2018. Two samples weighing approximately 4kg were taken from exposed faces of the Vaalhoek Reef, in two separate underground localities of previous mining. Two samples were also taken of Thelma Leader mineralisation located in underground exposures adjacent to the Vaalhoek Dyke. These samples also weighed approximately 4 kg each. All samples were composites of rock chipped over the reef width. The four samples were submitted for Bottle Roll testwork at SGS Barberton, which is discussed under the Metallurgical section.</p> <p>The smallest split drillcore sample taken was 15 cm in length. After crushing and pulverising the core sample, a 30 g cupel was utilised for analysis. Low core recoveries resulted in reverting to RC drilling for evaluation purposes. For the RC drilling conducted at the Theta Project, the mass of recovered sample obtained was recorded on a per metre drilled basis, with approximately 3 kg of sample per metre run, being split off by means of a 3-tier riffle splitter for submission to SGS Laboratories in Barberton. Assays pertaining to the Theta Project were conducted by means of gold by fire assay with a gravimetric and/or flame atomic absorption spectrometry ("AAS") utilising a 30 g cupel.</p>
Drilling techniques	Drill type (e.g. core, reverse circulation, open-hole hammer, rotary air blast, auger, Bangka, sonic, etc.) and details (e.g. core diameter, triple or standard tube, depth of diamond tails, face-sampling bit or other type, whether core is oriented and if so, by what method, etc.).	<p>a) Underground/Hard Rock Projects:- All historic (pre 2007/2008) Mineral Resource evaluation drilling for the underground projects was conducted in the form of diamond drilling. Information regarding drilling diameter, drill tube type and core orientation is not available or discernible for the earlier 1995/1996 drilling as the core is no longer available. Only core loss, intersection length and grade (g/t) are recorded with various levels of geological lithological information. Due to the age of the data in question and the non-availability of the historical drill core, information regarding drilling diameter, drill tube type, core orientation is not available. More recent drillhole data (inclusive of diamond, RC and auger) from 2008 onward is considered to be high quality as it was conducted to updated industry standards with the incorporation of assay QAQC where blanks and certified reference material ("CRM") were inserted for monitoring purposes. Core drilling utilised an NQ (47.6 mm) drill bit. Details pertaining to earlier drilling programs' core orientation are not available. Due to poor diamond drillcore recoveries during the 2017-2019 drilling campaign, core orientation was not conducted.</p> <p>b) Open Pit or Eluvial Projects:- Drilling on the eluvial deposits took place under the auspices of Horizon Blue Resources and is regarded as being of high quality due to good survey control and inclusion of QAQC practices. The main drilling method (95% of drillholes) utilised to evaluate these projects was reverse circulation (4.5 inch (115 mm) and 6 inch (150 mm) diameter) drilling, vertical reverse circulation drillholes, with or without temporary casing depending on ground condition in the vicinity of the various drill sites. Rotary core drilling (NQ size with 75.7 mm outside diameter and 47.6 mm inside diameter) was utilised in 5% of the drillholes on these projects. More recent drillhole data (inclusive of diamond, RC and auger) from 2008 onward is considered to be of high quality as it was conducted to updated industry standards with the incorporation of assay QAQC where blanks and certified reference material ("CRM") were inserted for monitoring purposes. Core drilling utilised an NQ (47.6 mm) drill bit. Details pertaining to earlier drilling programs' core orientation are not available. Due to poor diamond drillcore recoveries during the 2017-2019 drilling campaign, core orientation was not conducted.</p>

SECTION 1: SAMPLING TECHNIQUES AND DATA		
Criteria	Explanation	Detail
		<p>c) Tailings Projects:- Drilling on the tailings projects was conducted by means of small diameter (45 mm and 50 mm) auger drilling. Drillhole positions have been surveyed by TGM utilising a GPS based Total station. All holes were drilled vertically.</p>
Drill sample recovery	Method of recording and assessing core and chip sample recoveries and results assessed.	<p>a) Diamond Drilling:- Information regarding the 1995/1996 recoveries is not available. However, during the 2008 and 2012/2013 drilling campaigns the recoveries were recorded.</p> <p>Diamond drill core recoveries were recorded during the 2013 drilling programmes, which was managed by Minxcon Exploration (Pty) Ltd. Core recovery percentage was calculated for each drill run. Sample recoveries were maximised through drilling techniques (diamond drilling), however drilling recoveries versus grade relationships were not assessed.</p> <p>During the 2017-2019 drilling campaign consistent and accurate records relating to core and RC drill sample recovery were maintained on a per sample basis. Diamond drill samples were measured on a per sample basis and related back to the recorded drill run length versus the length of drill core recovered, which was then presented as a percentage. The average drill recovery achieved during the diamond drilling campaign was approximately 65%, with at least 33.3% of samples achieving recoveries of 50% or less. This low recovery resulted in reverting to RC drilling as a means of obtaining representative drill data for evaluation purposes.</p> <p>b) RC Drilling:- Details regarding the chip sample recovery of the historical RC drilling for the eluvial project are not available or existent in Minxcon's data records. For the RC drilling conducted at the Theta Project, the mass of recovered sample obtained was recorded on a per metre drilled basis, with approximately 3 kg of sample per metre run, being split off by means of a 3-tier riffle splitter for submission to SGS Laboratories in Barberton.</p>
	Measures taken to maximise sample recovery and ensure representative nature of the samples.	<p>Owing to the historical nature of the data in question (prior to 2005), measures taken to maximise sample recovery and ensure the representative nature of the samples are not known.</p> <p>During the 2008, 2012/2013 and 2017-2019 drilling campaign, sample recoveries were maximised through utilising appropriate drilling techniques depending on the deposit in question. In order to ensure the representative nature of the drilled intersections and due to the dip of the reefs being very shallow at between 3° to 12°, drillholes were drilled vertically in order to obtain an intersection as close to normal as possible. Owing to low core recoveries achieved in the 2017-2019 drilling campaign, RC drilling was utilised to maximise sample recovery.</p>
	Whether a relationship exists between sample recovery and grade and whether sample bias may have occurred due to preferential loss/gain of fine/coarse material.	<p>Sample recovery versus grade was not assessed due to the lack of historical drill core and sample rejects, as well as due to the low diamond drilling sample recovery experience during the 2017-2019 drilling campaign. Sample recovery and grade relations with regard to the RC drilling was not possible due to not having a historical RC dataset to compare with. It is Minxcon's view that samples recording a core loss would result in a net negative bias, resulting in a potentially lower reported gold value. Twinning of these holes might serve to support this theory.</p>
Logging	Whether core and chip samples have been geologically and geotechnically logged to a level of detail to support appropriate Mineral Resource estimation, mining studies and metallurgical studies.	<p>Historical drillholes (pre-2007/2008) in most cases have no original drillhole logs available for review. Summary lithological strip logs or MS Excel™ logs are available in most cases however and present lithological changes and reef positions. It is Minxcon's view that the level of detail available is still supportive and appropriate for Mineral Resource estimation. This level of detail has been considered in allocation of Mineral Resource classification.</p> <p>All 2008 drillholes were geologically logged including the deflections (or wedges) and the 2012/2013, as well as the 2017-2019 drilling campaign drillholes were both geologically and geotechnically logged. It is Minxcon's view that logging was done to a level of detail appropriate to support Mineral Resource estimation.</p>
	Whether logging is qualitative or quantitative in nature. Core (or costean, channel, etc.) photography.	<p>No detailed drillhole logs are available for the historical (pre-2007/2008) surface drilling. No core or core photography is available for review. The 2008 and 2012/2013 logging was qualitative in nature and core photos of all intersections were also taken. Logging conducted during the 2017-2019 drilling campaign was also qualitative in nature. All drill core and reference RC Chip sample trays were photographed and archived for record purposes.</p>
	The total length and percentage of the relevant intersections logged.	<p>Historical drillholes (pre-2007/2008) in most cases have no original drillhole logs available for review. Summary lithological strip logs or MS Excel™ logs are available in most cases however and present lithological changes and reef positions. Based on the information available it is assumed that all historical intersections represented in the Mine Resource estimation dataset were logged. All drilling</p>

SECTION 1: SAMPLING TECHNIQUES AND DATA		
Criteria	Explanation	Detail
		and relevant intersections relating to 2007 through to, and including the 2017-2019 drilling programme were logged. The logging information per Project is presented in the full CPR document and described in detail.
Sub-sampling techniques and sample preparation	If core, whether cut or sawn and whether quarter, half or all core taken.	<p>It is not known how core was split in historical drilling (pre-2007/2008) campaigns. It is assumed that core was split as has been routine exploration practice. However, sampling/core records/libraries or protocols for this period are not available for review.</p> <p>In later drilling programmes (including the 2017-2019 drilling campaign) core was sawn in half lengthwise down the core axis. Once the core had been split the core was sampled along lithological boundaries. The smallest sample that was taken was 15 cm which was governed by the low core recovery, as well as the minimum weight required for a laboratory sample.</p> <p>Individual samples for NQ cores were 20 cm long. Reef samples were >10 cm and <40 cm.</p>
	If non-core, whether riffled, tube sampled, rotary split, etc. and whether sampled wet or dry.	Historical Protocols pertaining to the RC and auger drilling sample splitting are not available for scrutiny and thus unknown. During the 2017-2019 RC drilling programme, samples were dry sampled and riffle split through a 3-tier riffle splitter
	For all sample types, the nature, quality and appropriateness of the sample preparation technique.	For historical diamond drilling (pre-2007/2008) no protocols pertaining to sample preparation techniques are available for scrutiny. Recent (inclusive of the 2017-2019 drilling campaign) drilling sampling preparation and its appropriateness is in line with industry practice.
	Quality control procedures adopted for all sub-sampling stages to maximise representivity of samples.	<p>Historical (pre-2007/2008) historical sub-sampling techniques were not available for review.</p> <p>All later drilling programmes utilised blanks and certified reference materials in order to maximise representivity of samples. In the 2017-2019 drilling campaign, coarse duplicates were added to the QAQC programme to test repeatability and thus representivity of samples.</p>
	Measures taken to ensure that the sampling is representative of the in situ material collected, including for instance results for field duplicate/second-half sampling.	<p>Pertaining to historical (pre-2007/2008) drilling programmes, sub-sampling techniques were not available for review. In 2008, only blanks and certified reference material were used. No field duplicate/second –half or subsequent quarter sampling was conducted to Minxcon's knowledge.</p> <p>Later drilling programmes utilised only blanks and certified reference material. No field duplicate/second–half or subsequent quarter sampling was conducted. In the 2017-2019 drilling campaign, coarse field duplicates were added to the QAQC programme to test repeatability and thus representivity of samples. Out of 292 duplicates taken, three were identified as outliers. Once these were removed from the dataset, a correlation coefficient of 0.9683 was achieved, presenting very high correlation, thus supporting the view of sample representivity.</p>
	Whether sample sizes are appropriate to the grain size of the material being sampled.	<p>Pre-2007/2008: Not known. Historical sample size taken were not recorded.</p> <p>Later programmes considered sample length versus core diameter together with assay laboratory techniques and protocols to ensure sample sizes were appropriate relative to the material in question being sampled. It is Minxcon's view that the sample sizes take are appropriate to the gold grain size being sampled due to the fact that out of 292 duplicates taken (2017-2019 drilling programme), three were identified as outliers. Once these were removed from the dataset, a correlation coefficient of 0.9683 was achieved, presenting very high correlation, thus supporting the view of sample representivity.</p>
Quality of assay data and laboratory tests	The nature, quality and appropriateness of the assaying and laboratory procedures used and whether the technique is considered partial or total.	<p>Historical underground channel chips were reported in dwt, it is assumed that only fire assay was utilised and it is assumed that the technique represents total analysis.</p> <p>In 2008, all diamond core samples including blanks and certified reference material ("CRM") were dispatched to Set Point Laboratories ("Set Point") in Isando, Johannesburg, South Africa. Set Point is a SANAS certified laboratory, in accordance with the recognised international standard ISO/IES 17025:2005, with accreditation number T0223. The samples were analysed for Gold ("Au") by standard fire assay with ICP finish, and specific gravity ("SG") analysis were conducted on selected samples. It is assumed that the technique represents total analysis.</p> <p>Up to May 2007, all RC samples were sent to ALS Chemex Laboratory. From May 2007 onwards, RC samples were sent to Performance Laboratories (now SGS Performance Laboratories) and core samples to ALS Chemex (which is SANAS accredited) for fire assay by lead separation and AA finish. Each sample was also analysed for a spectrum of 34 metals using Inductively Coupled Plasma ("ICP") techniques. It is assumed that the technique represents total analysis.</p>

SECTION 1: SAMPLING TECHNIQUES AND DATA		
Criteria	Explanation	Detail
		<p>In 2017, samples from drillholes V6 and V8 including blanks and certified reference material were dispatched to Super Laboratory Services (Pty) Ltd ("Super Labs") in Springs, South Africa. Super Labs is a SANAS certified laboratory, in accordance with the recognised international standard ISO/IES 17025:2005, with accreditation number T0494. The assay samples are 50 g samples in mass and are assayed for gold (Au) by means of fire assay with gravimetric finish. It is assumed that the technique represents total analysis.</p> <p>For the 2017-2019 drilling campaign, all drillhole samples were sent to SGS Performance Laboratories in Barberton. SGS Performance Laboratories, Barberton is a SANAS certified laboratory, in accordance with the recognised international standard FAA303, with accreditation number T0565. Assays pertaining to the Theta Project were conducted by means of gold by fire assay with a gravimetric and/or flame AAS utilising a 30 g cupel. This assay technique is viewed as being total.</p>
	For geophysical tools, spectrometers, handheld XRF instruments, etc., the parameters used in determining the analysis including instrument make and model, reading times, calibrations factors applied and their derivation, etc.	No assay methods other than those conducted by laboratories as mentioned above were utilised in the generation of any of the TGM projects sampling database.
	Nature of quality control procedures adopted (e.g. standards, blanks, duplicates, external laboratory checks) and whether acceptable levels of accuracy (i.e. lack of bias) and precision have been established.	<p>No records of Assay QAQC are available for the historical data due to the age there-of (i.e. pre-1946 for channel chip sampling, and for drilling predating 2007/2008) and due to the accepted practices in place at the time.</p> <p>Drilling campaigns conducted post 2007/2008 and the accompanying sampling was conducted according to industry standards. QAQC measures were implemented by regular insertion of blanks and standards into the sampling stream. Minxcon considers that the QAQC measures, as well as data used for Mineral Resource estimation, were of adequate quality. Approximately 17% of the samples sent to the laboratory represented assay control material. Minxcon is of the opinion that an adequate number of control samples were utilised during this drilling programme. No field duplicates were however used during the 2008 drilling and sampling programmes.</p> <p>During the 2012/2013 exploration programme, the project was stopped due to budgetary constraints and the completed drillholes were not assayed at the time.</p> <p>For the 2013 drilling programme the samples were analysed in 2017 and a total of 84 samples including blanks and certified reference material were dispatched to Super Labs. Two CRMs, namely AMIS0016 and AMIS0023, and silica sand blanks were used in the sampling sequence. Roughly every fifth sample inserted in the sampling sequence was a QAQC sample. A total of two AMIS0023, two AMIS0016, five duplicates and six blank samples were used. Approximately 18% of the samples sent to the laboratory represented assay control material. Minxcon is of the opinion that an adequate number of control samples were utilised.</p> <p>During the 2017-2019 drilling programme the CRMs and blanks were inserted at predetermined positions in the sampling sequence, namely: analytical blank samples were placed at the beginning and at the end of a drillhole. With the diamond drilling control samples were placed in the sampling stream at every tenth sample, with a sequential rotation between a blank, CRM and duplicate. With the RC drilling, this was similarly done, but at every twentieth sample position. In both cases the control sample spacing was based upon the batch size utilised by the laboratory in order to ensure each tray included at least one blank and an additional control sample during sample preparation and analysis.</p> <p>Approximately 2.75% of the samples sent to the laboratory represented CRM and 4.5% represented analytical blanks and 1.3% represented coarse duplicates. These samples are in addition to the in-laboratory assay conducted by the laboratory which traditionally adds up to 20% control samples to the total sample stream, usually incorporating a CRM as well as an analytical blank and two duplicate samples to each sample batch. Minxcon is of the opinion that an adequate number of control samples were utilised during this drilling programme.</p>
Verification of sampling and assaying	The verification of significant intersections by either independent or alternative company personnel.	<p>No verification of historical assay results is currently possible due to the historical nature of the data in question and the non-availability of the core.</p> <p>Minxcon verified the historically bagged samples for drillholes V6 and V8 for accuracy and representativeness before sending them to the laboratory in 2017. Those samples that were not representative or missing were re-sampled from the remaining core at TGM.</p>

SECTION 1: SAMPLING TECHNIQUES AND DATA		
Criteria	Explanation	Detail
		<p>Minxcon reviewed all historical datasets chip sampling and the historical drilling attributed to the various historical operations, as well as digital plans (scanned DXF plans of sampling plans) and found that captured sample positions had good agreement with those in the digital dataset. In addition, different versions of the underground sampling file were found and cross validated to test for data changes or eliminations. These were corrected where applicable.</p> <p>Minxcon reviewed, verified and cross-checked captured assays relating to the 2008 drilling dataset by means of checking for transfer mistakes, gaps and overlaps in sampling intervals and also checked that all reef composites were correctly calculated for each reef intersection, before calculating the weighted mean of drillhole points with multiple intersections of wedges.</p> <p>Minxcon conducted checks on sampling during the 2017-2019 drilling programme by means of standard assay QAQC procedures and reviewing and cross-checking the .pdf assay results provided by the laboratory and those copied into the database utilised for evaluation. In addition, reviews of the sampling process were conducted by Minxcon personnel other than those managing the programme, namely the then Competent Person Mr Uwe Engelmann, and Mr Paul Obermeyer, the then Minxcon Mineral Resource Manager.</p>
	Discuss any adjustment to assay data.	No adjustments were made to raw assay data according to Minxcon's knowledge.
	Documentation of primary data, data entry procedures, data verification, data storage (physical and electronic) protocols.	Not known. Historical data capture and data entry procedures were not available for review. The 2007/2008 and 2013 exploration programmes were logged and captured on hardcopy. These were then transferred to MS Excel™. Minxcon currently only has the data in this digital format for verification purposes. During the 2017-2019 drilling campaign, all logging and sampling were logged and captured on hardcopy and then captured in MS Excel™. Assay results were received from the laboratory in MS Excel™ .csv format as well as .PDF, thus allowing verification and comparison between hardcopy, source and digital data files.
	The use of twinned holes.	No twinned holes were drilled.
	Accuracy and quality of surveys used to locate drillholes (collar and down-hole surveys), trenches, mine workings and other locations used in Mineral Resource estimation.	<p>TGM utilised a handheld GPS for the purpose of locating historical adits and mine entrances, which in turn have been utilised in conjunction with historical survey data in positioning the historical underground workings in 3D. Historical survey plans with plotted survey peg positions and elevations are available for most of the historical underground operations. These pegs were installed by mine surveyors relative to fixed local mine datum's. The survey pegs and workings have been digitised in ARCVIEW GIS 10™.</p> <p>Each data point and stretch value on the original assay plans was marked and annotated with a reef width and gold grade. Assay plan images were imported into GIS and co-ordinates converted from a local grid co-ordinate (WG31) system to a WGS84 grid system. The plans were then captured into Datamine Studio 3™. The captured assay points were plotted on a plan of the underground workings to ensure that the points plotted correctly relative to development and stoping. The sampling has in turn been fixed to the underground development and stoping voids. It is Minxcon's opinion that sample positional accuracy would be within 5 to 10 m of the original sample point (within acceptable limits of a GPS). Drillhole collars were also located by means of handheld GPS co-ordinates.</p> <p>Assay plan images were imported into GIS and co-ordinates converted from a local grid co-ordinate system to a WGS84 grid system. The plans were then captured into Datamine®. The captured assay points were plotted on a plan of the underground workings to ensure that the points plotted correctly relative to development and stoping.</p> <p>Historically, sampling points were measured by means of measuring tape and the resultant offsets plotted on the sampling and development plans.</p> <p>Information pertaining to the instrument used for downhole survey conducted before and including the 2007/2008 drilling programmes is not available During the 2012/2013 drilling programme an EZ-Trac with EZ Com was used.</p> <p>Drillholes drilled at the Theta Project did not have downhole surveys conducted due to all being drilled vertically and due to them all being under 200 m in depth. Drillhole collars were located by two means. Of the 371 holes drilled some 99 collars were surveyed utilising an RTK Trimble R8 GPS Survey Total Station, while the balance was recorded by means of handheld GPS. TGM complete a LIDAR survey over the Theta Project in March 2019 which was then used to re-elevate the collar positions to the new LIDAR surface for improved accuracy. The 3D geological model was updated in June 2019 and the Mineral Resource was adjusted accordingly.</p>
Location of data points	Specification of the grid system used.	The grid system used is Hartebeeshoek 1994, South African Zone WG31.
	Quality and adequacy of topographic control.	Minxcon utilised the GPS co-ordinates provided by TGM for the adit positions, as well as ventilation openings to assist in verifying and fixing the underground workings in 3D space. Very good correlation between the digital topography and the underground mining profiles was found. The tailings and rock dump projects were surveyed utilising standard survey methods (Survey total station) and detailed

SECTION 1: SAMPLING TECHNIQUES AND DATA		
Criteria	Explanation	Detail
		<p>topographical data collected. This data was subsequently rendered as digital contour plans. A LIDAR survey was conducted in March 2019 and was compared to the original digital topography utilised in the reef modelling. Discrepancies were found to be small with negligible impact on the geological model or the reef block models. The 3D geological model was revised in June 2019 and the Mineral Resource adjusted accordingly. There was an overall increase of 9% in the ounces in the Mineral Resource for the Theta Project due to the changes in the reef elevation and reef outcrop positions.</p>
Data spacing and distribution	Data spacing for reporting of Exploration Results.	<p>In the stoping areas, the mean channel chip sample grid spacing was approximately on a 5 m x 5 m grid, while on development in older areas samples were taken at about 5 m to 6 m intervals, while in more recent areas sample sections were taken at between 2 m to 3 m spacing. Available information shows that diamond drillholes were drilled on an irregular grid of between 200 m to 500 m.</p> <p>Owing to the more advanced investigation stage (i.e. Mineral Resources and Ore Reserves), no Exploration Results have been reported.</p> <p>In the stoping areas, the sample stretch values were spaced approximately at 15 m on dip and 4 m on strike, while in more detailed areas sample spacing was found to be as little as 3 m between points. In the development, stretch values spacing varied from 4 m to 20 m, while in more detailed areas sample spacing is seen to be as close as 3 m.</p> <p>Drillhole spacing for the underground projects varies significantly and is considered during Mineral Resource classification. In one specific case (Vaalhoek) two drillholes (V6 and V8) did not significantly affect the Mineral Resource estimation as they were beyond the variogram range of the sample points (1,000 m) as Minxcon did not include the drillhole data with the stretch value data. They did however prove continuity of the reef.</p> <p>For the Glynn's Lydenburg and Blyde TSF projects, auger drilling was conducted on a 25 m x 25 m grid spacing, while on the TGM Plant TSF auger drilling was conducted on an approximate 50 m x 50 m grid.</p> <p>The Hermansburg eluvial deposit was drilled on an approximate 25 m x 25 m grid, while the DG deposits were drilled on an approximate 20 m x 20 m by 25 m x 25 m grid spacing, depending on local topography and access.</p>
	Whether the data spacing and distribution is sufficient to establish the degree of geological and grade continuity appropriate for the Mineral Resource and Ore Reserve estimation procedure(s) and classifications applied.	<p>It is Minxcon's opinion that drillhole and sample spacing is adequate for the purpose of conducting meaningful Mineral Resource estimation in and around stoping areas due to the density of the chip sampling data. It is Minxcon's view that the drillhole spacing pertaining to the Theta Project conducted during the 2017-2019 drilling programme is adequate for the purpose of conducting Mineral Resource estimation. Spacing per reef is viewed as being appropriate to the Mineral Resource categories applied.</p>
	Whether sample compositing has been applied.	<p>All channel chip sample points within the underground operations database represent full reef composites. Full reef composites were applied to drillholes belonging to the underground operations due to the inherent narrow nature of the reefs concerned. All eluvial, TSF drillholes and rock dump sample points were composite at fixed downhole sample intervals for the purposes of conducting full 3D Mineral Resource Estimations on these types of deposits. During the 2017-2019 drilling programme, in thin reef environments with reefs of <1 m (Upper Theta, Lower Theta and Beta Reefs) diluted (to 1 m) reef composites were utilised for evaluation purposes due to the minimum sample width obtained during the RC drilling being 1 m. In thick reef environments (Upper Rho, Lower Rho, Bevetts and Shale reefs), individual original sample widths of 1 m were maintained for utilisation in 3D estimation.</p>
Orientation of data in relation to geological structure	Whether the orientation of sampling achieves unbiased sampling of possible structures and the extent to which this is known, considering the deposit type.	<p>Concordant reefs are all near horizontal and as such these dip at between 3° to 12° to the west and strike in a north-south direction. Drillholes were drilled vertically (-90° dip) to intercept the mineralised shear zones at a near perpendicular angle in order that the sampling of the drill core minimises the sampling bias. Chip sampling in concordant reef environments was conducted normal to reef dip. It is Minxcon's view that sampling orientation has attempted to reduce sample bias with respect to angle of intersection. All intersections represented corrected reef widths.</p> <p>Discordant reef as encountered at Rietfontein is vertical to sub-vertical. Drillholes were orientated at angles to intercept the mineralised shear zones at as near a perpendicular angle in plan and acute angle in section as possible in order that the sampling of drill core minimises the sampling bias. Chip sampling was conducted normal to reef dip. It is Minxcon's view that sampling orientation has attempted to reduce sample bias with respect to angle of intersection. All intersections represented corrected reef widths.</p>

SECTION 1: SAMPLING TECHNIQUES AND DATA		
Criteria	Explanation	Detail
		All sampling of the TSF was conducted vertically. This is normal to the orientation of deposition and is therefore achieves unbiased sampling
	If the relationship between the drilling orientation and the orientation of key mineralised	Available information indicates that the drilling orientation provides reasonably unbiased sampling of the mineralisation zones.
Sample security	The measures taken to ensure sample security.	<p>Measures taken to ensure sample security pertaining to the historical chip sampling are not available due to the historical nature of the data in question.</p> <p>Measures taken to ensure sample security during historical drilling programmes (1995/1996 and 2008 drilling) are not available due to the historical nature of the data in question. During 2012/2013 all core samples were stored in a locked facility prior to dispatch to the laboratory. The samples from the 2013 drilling campaign were bagged and labelled in 2013 but were not sent away to a laboratory for assayed due to the project ending prematurely. The samples were stored at the TGM Plant in Pilgrims Rest and delivered to the Minxcon Exploration offices in Johannesburg in November 2017 to check and verify the previously bagged samples. A standard chain of custody was implemented during the 2017-2019 drilling campaign. Immediately when the core arrived in the core yard daily, the geologist or core yard manager was required to sign the core shed register (core) after inspecting the core against the reported drilled metres in acknowledgement of having received the core in good condition. On a weekly basis (or more often when required) samples were despatched directly to the analytical laboratory. The Chain of Custody for the core and samples utilised by Minxcon in the 2017-2019 drilling programme was congruent with that utilised in the 2008 and 2012/2013 drilling programs under the management of Agere.</p>
Audits or reviews	The results of any audits or reviews of sampling techniques and data.	<p>Minxcon reviewed all historical datasets attributed to the various projects comprising the Mineral Resources, historical plans and sections as well as digital plans (scanned DXF plans of sampling plans) and found that historically captured sample positions had good agreement with those in the digital dataset. In addition, different versions of the underground sampling files were found and cross validated to test for data changes or eliminations. Minxcon also digitised a series of plans or sampling points and stretch values which were used in the various estimations. Minxcon was not able to audit or review the sampling techniques in practice due to the historical nature of the data in question.</p> <p>Minxcon is not aware of any other audits that have been conducted on the Mineral Resources.</p>

SECTION 2: REPORTING OF EXPLORATION RESULTS		
Criteria	Explanation	Detail
Mineral tenement and land tenure status	Type, reference name/number, location and ownership including agreements or material issues with third parties such as joint ventures, partnerships, overriding royalties, native title interests, historical sites, wilderness or national park and environmental settings.	<p>The mining rights are held under Transvaal Gold Mining Estates Limited ("TGME"), a 74% indirect subsidiary of TGM. The mineral rights 83MR, 340MR, 341MR, 358MR and 433MR have been granted, registered and executed, held over certain Mineral Resource areas. Their accompanying environmental and social permits are also executed.</p> <p>The mining rights 10161MR and 10167MR have been granted and are pending execution. The mining rights 330MR and 198MR are still in the approval process.</p> <p>A Section 102 amendment process for inclusion of Theta Project into 83MR is currently underway, with the environmental and socio-economic studies, as well as water use licence application process, following prescribed regulatory timelines. It is noted that the proposed underground operations may require revised mine work programmes to be approved, as well as environmental, social and water use licences.</p>
	The security of the tenure held at the time of reporting along with any known impediments to obtaining a licence to operate in the area.	<p>TGM is required to comply with DMRE regulations and instructions timeously in order to receive executed rights, as well as for the currently active rights to remain in force. Minxcon notes that a few years have lapsed since the last formal DMRE communication on 330MR and 198MR, and notes that the security of these rights may be at risk.</p> <p>The 83MR Section 102 application is following timelines as stipulated by applicable regulations and guided by government departments and procoesses.</p> <p>The Mineral Resources are located within the above permit areas as per the figure below.</p>

SECTION 2: REPORTING OF EXPLORATION RESULTS		
Criteria	Explanation	Detail
Exploration done by other parties	Acknowledgment and appraisal of exploration by other parties.	Acknowledgement is hereby made for the historical exploration conducted from 1977 to 1982 by Placid Oil and Southern Sphere over the northern areas over the TGM holdings. From 1982 to 1992, Rand Mines conducted sporadic alluvial prospecting along the Blyde River, limited surface diamond drilling, re-opening of old workings and extensive exploration programmes around the town of Pilgrims Rest. TGME and Simmer & Jack conducted drilling, geochemical soil sampling, trenching and geological mapping.
Geology	Deposit type, geological setting and style of mineralisation.	<p>Epigenetic gold mineralisation in the Sabie-Pilgrims Rest Goldfield occurs as concordant and discordant (sub-vertical) veins (or reefs) in a variety of host rocks within the Transvaal Drakensberg Goldfield, and these veins have been linked to emplacement of the Bushveld Complex.</p> <p>Mineralisation in the region occurs principally in concordant reefs in flat, bedding parallel shears located mainly on shale partings within the Malmani Dolomites. These bodies are stratiform, and are generally stratabound, and occur near the base of these units.</p> <p>The discordant reefs (or cross-reefs) are characterised by a variety of gold mineralisation styles. At Rietfontein, a sub-vertical quartz-carbonate vein occurs which reaches up from the Basement Granites and passes to surface through the Transvaal. They are found throughout the Sabie-Pilgrims Rest Goldfield, and are commonly referred to as cross reefs, blows, veins, and leaders and exhibit varying assemblage of gold-quartz-sulphide mineralisation generally striking northeast to north-northeast. They vary greatly in terms of composition, depth and diameter. In addition to the above, more recent eluvial deposits occur on the sides of some of the hills and are thought to represent cannibalised mineralised clastic material resulting from the erosion of underlying reefs. Gold mineralisation is accompanied by various sulphides of Fe, Cu, As and Bi.</p>
Drillhole Information	A summary of all information material to the understanding of the exploration results including a tabulation of the following information for all Material drillholes: * easting and northing of the drillhole collar * elevation or RL (Reduced Level – elevation above sea	A summary of the data types and the number of data attributable to each project is presented in the table below. It should be noted that all the projects listed are historical mining areas and do not constitute exploration projects in the true sense of the word. However, detailed drillhole summary tables are presented in the CPR in the appropriate sections pertaining to Exploration Targets. It should be noted that the numbers presented for drillholes in the table below represent all drillhole records, regardless of the status of the data concerned.

SECTION 2: REPORTING OF EXPLORATION RESULTS						
Criteria	Explanation	Detail				
	level in metres) of the drillhole collar * dip and azimuth of the hole * down hole length and interception depth * hole length.		Project Area	Sampling Data Types	Historical datasets (Pre - 2007/2008) Quantity (Incl. Wedges)	Recent Datasets Quantity
		Rietfontein	Drillhole Data	8	-	
			Channel Chip Sample Data	2,265	-	
		Beta	Drillhole Data	7	20	
			Channel Chip Sample Data	4,553	-	
		Frankfort	Drillhole Data	15	59	
			Channel Chip Sample Data	3,187	864	
		CDM	Drillhole Data	115	-	
			Channel Chip Sample Data	24,483	-	
		Olifantsgeraamte	Drillhole Data	1	-	
			Channel Chip Sample Data	316	-	
		Vaalhoek	Drillhole Data	16	8	
			Channel Chip Sample Data	3,836	-	
			Stretch Values	1,472	-	
		Glynn's Lydenburg	Drillhole Data	-	-	
			Channel Chip Sample Data	26,435	-	
			Stretch Values	872	-	
		Theta Project (Theta Hill, Browns Hill & Iota section of Columbia Hill)	Drillhole Data	263	371	
			Trench Sampling	-	10	
			Channel Chip Sample Data	7,472	-	
		Columbia Hill (remaining)	Drillhole Data	26	-	
			Channel Chip Sample Data	14,478	-	
		Hermansburg	RC Drillhole Data	-	79	
		DG1	RC Drillhole Data	-	-	
		DG2	RC Drillhole Data	-	221	
		DG5	Grab Samples	-	≈100	
			RC Drillhole Data	-	19	
		Glynn's Lydenburg TSF	Auger Drillhole Data	-	140	
		Blyde TSFs (1, 2, 3, 3a, 4, 5)	Auger Drillhole Data	-	86	
		TGM Plant	Auger Drillhole Data	-	34	
		Vaalhoek (Rock dump)	Bulk Sampling Data	-	1	
			Trench Sampling Data	-	13	
			Sampling Pit Data	-	57	
		South East (DGs) (Rock dump)	Bulk Sampling Data	50	-	
		Peach Tree (Rock dump)	Bulk Sampling Data	8	-	
		Ponieskrantz (Rock dump)	Bulk Sampling Data	10	-	
		Dukes Clewer (Rock dump)	Bulk Sampling Data	13	-	
	If the exclusion of this information is justified on the basis that the information is not Material and this exclusion does not detract from the understanding of the report, the Competent Person should clearly	All the available drillholes on all projects and project types that were historically sampled and had the assay result available, were used for Mineral Resource estimation with the exception of four drillholes (in the case of Rietfontein) where out of eight drillholes, a total of four were excluded from the estimation due to excessive poor core recovery. All 10 drillholes drilled in 2012/2013 as well as three drillholes drilled in 2008 were only used for geological modelling due to the fact that the project was stopped due to budget constraints and the mineralised zones were never assayed.				

SECTION 2: REPORTING OF EXPLORATION RESULTS		
Criteria	Explanation	Detail
	explain why this is the case.	
Data aggregation methods	In reporting Exploration Results, weighting averaging techniques, maximum and/or minimum grade truncations (e.g. cutting of high grades) and cut-off grades are usually Material and should be stated.	All chip samples and drillhole samples were agglomerated. Data type biases were not investigated due to the small number of drillhole intersections. Where stretch values were used in the estimation these were composited to a 3 m composite based on a minimum stretch length. These values were treated separately and not included in the chip sample database. Areas utilising stretch values were immediately relegated to Inferred Mineral Resource classification. During the 2017-2019 drilling programme, in thin reef environments with reefs of <1 m (Upper Theta, Lower Theta and Beta Reefs) diluted (to 1 m) reef composites were utilised for evaluation purposes due to the minimum sample width obtained during the RC drilling being 1 m. In thick reef environments (Upper Rho, Lower Rho, Bevetts and Shale Reefs), individual original sample widths of 1 m were maintained for utilisation in 3D estimation.
	Where aggregate intercepts incorporate short lengths of high grade results and longer lengths of low grade results, the procedure used for such aggregation should be stated and some typical examples of such aggregations should be shown in detail.	All chip samples and drillhole samples were agglomerated. Data type biases were not investigated due to the small number of drillhole intersections. Where stretch values were used in the estimation these were composited to a 3 m composite based on a minimum stretch length. These values were treated separately and not included in the chip sample database. Areas utilising stretch values were immediately relegated to Inferred Mineral Resource classification. During the 2017-2019 drilling programme, in thin reef environments with reefs of <1 m (Upper Theta, Lower Theta and Beta Reefs) diluted (to 1 m) reef composites were utilised for evaluation purposes due to the minimum sample width obtained during the RC drilling being 1 m. In thick reef environments (Upper Rho, Lower Rho, Bevetts and Shale reefs), individual original sample widths of 1 m were maintained for utilisation in 3D estimation.
	The assumptions used for any reporting of metal equivalent values should be clearly stated.	No metal equivalents were calculated.
Relationship between mineralisation widths and intercept lengths	If the geometry of the mineralisation with respect to the drillhole angle is known, its nature should be reported. If it is not known and only the down hole lengths are reported, there should be a clear statement to this effect (e.g. 'down hole length, true width not known').	For the historical drillhole intersections (as well as intersections pertaining to the 2017-2019 drilling campaign) no downhole lengths have been reported – only true reef widths have been recorded in the estimation database on the historical sampling plans and sections. All drilling was conducted near normal to bedding so is reef width would be very closely related to the intersection length due to the low dip of the orebody and the vertical drilling of the drillholes. Historical underground chip sampling is sampled normal to the dip of the reef so is therefore the true width.
		Only true width data is available. All significant grades presented in the estimation dataset represent the value attributable to the corrected sample width and not the real sampled length.
Diagrams	Appropriate maps and sections (with scales) and tabulations of intercepts should be included for any significant discovery being reported. These should include, but not be limited to a plan view of drillhole collar locations and appropriate sectional views.	The TGM Mineral Resource is not a true greenfields exploration project but rather a mature mining operation with a wealth of historical underground chip sampling and drillhole intersections which have been collated, captured and digitised. The CPR has the detail diagrams of the sampling datasets for the various operations. These include chip samples and drillhole intersections.
Balanced reporting	Where comprehensive reporting of all Exploration Results is not practicable, representative reporting of both low	The various Mineral Resource estimations were conducted by Minxcon and are based upon the information provided by TGM. This Mineral Resource Report contains summary information for all historic sampling and drilling campaigns within the Project Area, as well as new data obtained during the evaluation drilling conducted at the Theta Project and provides a representative range and mean of grades intersected in the datasets.

SECTION 2: REPORTING OF EXPLORATION RESULTS																													
Criteria	Explanation	Detail																											
	and high grades and/or widths should be practiced to avoid misleading reporting of Exploration Results.																												
Other substantive exploration data	Other exploration data, if meaningful and material, should be reported including (but not limited to): geological observations; geophysical survey results; geochemical survey results; bulk samples – size and method of treatment; metallurgical test results; bulk density, groundwater, geotechnical and rock characteristics; potential deleterious or contaminating substances.	<p>Various exploration campaigns have been conducted over the years but not all information is available or relevant to the current Mineral Resource update. No other exploration data other than that presented for the purposes of the Mineral Resource estimation is therefore presented here. TGM has undertaken additional drilling at Columbia Hill (Iota), Theta Hill, Browns Hill and Iota (Theta Project). This data has been incorporated in the current Mineral Resource estimate.</p> <p>TGM has completed and is still in the process of completing metallurgical testwork and studies for the recoveries of the various reefs. This testwork all forms part of the feasibility study that is being completed.</p> <p>Grab samples taken at Beverly Hills and Desire mine were from old broken ore (sweepings) left in the stope panels. Random samples are taken from this broken ore where safe entry permits into the old stope panels. Samples are collected at the top, middle, and bottom of the stope panel. These samples are then delivered to Gold 1 or SGS laboratories for evaluation. The chip samples at Frankfort Beverly Hills Mine are taken on a 12-meter grid spacing, channels cut into the rock from top hangingwall contact to bottom footwall contact. The 25cm between the two parallel cuts is chipped out, bagged, and transported to the laboratories.</p> <p><u>Preliminary assay results are shown below. Further sampling inclusive of bench scale amenability to gravity and flotation concentration is in progress.</u></p> <p>Beverly Hills sweepings grabs – 15.79g/t and 4.37g/t Beverly Hills chip samples – 11.79g/t Desire sweepings grabs – 14.27g/t and 10.79g/t</p>																											
Further work	The nature and scale of planned further work (e.g. tests for lateral extensions or depth extensions or large-scale step-out drilling).	<p>The properties have a number of potential exploration targets that may increase the current Mineral Resource and Ore Reserve. These are spread over a number of the project areas and cover lateral extensions, depth extensions as well as compiling and re-interpreting historical datasets. The table below is a summary of the near-term potential exploration targets. The scale of the exploration depends on the available budget and therefore cannot be defined currently.</p> <table border="1"> <thead> <tr> <th>Project</th><th>Type of Potential</th><th>Comment</th></tr> </thead> <tbody> <tr> <td>Rietfontein</td><td>Lateral and depth extensions</td><td>Lateral extension is possible to the south which is untested as well as at depth below the current historical mining areas</td></tr> <tr> <td>Beta</td><td>Lateral extension</td><td>Lateral extension of the main beta "Payshoot"</td></tr> <tr> <td>CDM</td><td>Lateral extension</td><td>Lateral extension to the south toward Dukes' Hill South</td></tr> <tr> <td>Theta</td><td>Lateral extension</td><td>Lateral extension to the south on both Theta Hill and Browns Hill once 341MR is available. Lateral extension to the west and southwest at Iota</td></tr> <tr> <td>Frankfort</td><td>Lateral extensions</td><td>Lateral extension on Bevetts Reef at Frankfort Main and Beverly Hills to the NE</td></tr> <tr> <td>Vaalhoek</td><td>Depth extensions and open-pit opportunities</td><td>Near surface potential (open pit) exists on the Vaalhoek Reef and Thelma Leaders Reef</td></tr> <tr> <td>Glynn's Lydenburg</td><td>Shallow lateral extensions</td><td>The new model has identified new high-grade exploration targets for possible near surface open pit opportunities</td></tr> <tr> <td>Columbia Hill</td><td>Shallow lateral extensions</td><td>The new geological interpretation has identified Columbia Hill as a potential open pit target that will be drilled in the near future</td></tr> </tbody> </table> <p>This table excludes all the other historical mines that have not been investigated yet.</p>	Project	Type of Potential	Comment	Rietfontein	Lateral and depth extensions	Lateral extension is possible to the south which is untested as well as at depth below the current historical mining areas	Beta	Lateral extension	Lateral extension of the main beta "Payshoot"	CDM	Lateral extension	Lateral extension to the south toward Dukes' Hill South	Theta	Lateral extension	Lateral extension to the south on both Theta Hill and Browns Hill once 341MR is available. Lateral extension to the west and southwest at Iota	Frankfort	Lateral extensions	Lateral extension on Bevetts Reef at Frankfort Main and Beverly Hills to the NE	Vaalhoek	Depth extensions and open-pit opportunities	Near surface potential (open pit) exists on the Vaalhoek Reef and Thelma Leaders Reef	Glynn's Lydenburg	Shallow lateral extensions	The new model has identified new high-grade exploration targets for possible near surface open pit opportunities	Columbia Hill	Shallow lateral extensions	The new geological interpretation has identified Columbia Hill as a potential open pit target that will be drilled in the near future
Project	Type of Potential	Comment																											
Rietfontein	Lateral and depth extensions	Lateral extension is possible to the south which is untested as well as at depth below the current historical mining areas																											
Beta	Lateral extension	Lateral extension of the main beta "Payshoot"																											
CDM	Lateral extension	Lateral extension to the south toward Dukes' Hill South																											
Theta	Lateral extension	Lateral extension to the south on both Theta Hill and Browns Hill once 341MR is available. Lateral extension to the west and southwest at Iota																											
Frankfort	Lateral extensions	Lateral extension on Bevetts Reef at Frankfort Main and Beverly Hills to the NE																											
Vaalhoek	Depth extensions and open-pit opportunities	Near surface potential (open pit) exists on the Vaalhoek Reef and Thelma Leaders Reef																											
Glynn's Lydenburg	Shallow lateral extensions	The new model has identified new high-grade exploration targets for possible near surface open pit opportunities																											
Columbia Hill	Shallow lateral extensions	The new geological interpretation has identified Columbia Hill as a potential open pit target that will be drilled in the near future																											
	Diagrams clearly highlighting the areas of possible extensions, including the main geological interpretations and future drilling areas, provided this information is not	<p>The potential areas for the various mines have been detailed in the CPR. Detailed exploration strategy and budget has not been finalised due to the unknown available budget.</p>																											

SECTION 2: REPORTING OF EXPLORATION RESULTS		
Criteria	Explanation	Detail
	commercially sensitive.	

SECTION 3: ESTIMATION AND REPORTING OF MINERAL RESOURCES	
Explanation	Detail
Measures taken to ensure that data has not been corrupted by, for example, transcription or keying errors, between its initial collection and its use for Mineral Resource estimation purposes.	<p>Minxcon reviewed all historical datasets attributed to all the underground projects, as well as digital plans (scanned DXF plans of sampling plans) and found that captured sample positions had good agreement with those in the digital dataset except for a small number of chip samples (<1%), which Minxcon subsequently corrected. In addition, different versions of the underground sampling file were found and cross validated to test for data changes or eliminations over the years. Minxcon found that database integrity was maintained over time.</p> <p>The chip sampling data that was captured was also verified on an ad-hoc basis by different personnel as to the personnel that captured the data. Prior to estimation a duplicate check in Datamine Studio RM™ was carried out on the datasets to eliminate duplicate data point errors, and found that less than 2% of the population included duplicate captured sample points.</p> <p>Minxcon reviewed existing digital drillhole logs and assay sheets for the historical drilling relative to scans of drillhole strip logs and found very good agreement. In cases where errors were encountered, these were corrected and incorporated into a date-stamped database for sign-off prior to submission for Mineral Resource estimation.</p> <p>With regards to the 2017-2019 exploration campaign, assay data integrity was maintained by cross-validating MS Excel™ .csv assay results files from the laboratory with the .pdf files also provided by the Laboratory. Hard copy geological logs were kept as a means of referral with reference to the geological information captured in the project database.</p>
Data validation procedures used.	<p>Minxcon reviewed all historical datasets attributed to all the underground projects, as well as digital plans (scanned DXF plans of sampling plans) and found that captured sample positions had good agreement with those in the digital dataset except for a small number of chip samples (<1%), which Minxcon subsequently corrected. In addition, different versions of the underground sampling file were found and cross validated to test for data changes or eliminations over the years. Minxcon found that database integrity was maintained over time.</p> <p>The chip sampling data that was captured was also verified on an ad hoc basis by different personnel as to the personnel that captured the data. Prior to estimation a duplicate check in Datamine Studio RM™ was carried out on the datasets to eliminate duplicate data point errors, and found that less than 2% of the population included duplicate captured sample points.</p> <p>Minxcon reviewed existing digital drillhole logs and assay sheets for the historical drilling relative to scans of drillhole strip logs and found very good agreement. In cases where errors were encountered, these were corrected and incorporated into a date-stamped database for sign-off prior to submission for Mineral Resource estimation.</p> <p>With regards to the 2017-2019 exploration campaign, assay data integrity was maintained by cross-validating MS Excel™ .csv assay results files from the laboratory with the .pdf files also provided by the Laboratory. Hard copy geological logs were kept as a means of referral with reference to the geological information captured in the project database.</p>
Comment on any site visits undertaken by the Competent Person and the outcome of those visits.	<p>Minxcon personnel have consistently visited the gold properties in the Sabie-Pilgrims Rest area since 2007. Mr Uwe Engelmann, who is a Competent Person and who is responsible for the sign-off of the Mineral Resources, undertook a site visit to the Beta Mine on 15 December 2016, as well as on 23 November 2017 and 18 May 2018 to review the current RC and diamond drilling conducted at the Theta Project to inspect the drilling and sampling procedures. During the May visit Mr Engelmann also inspected the tailings storage facilities ("TSFs") and Vaalhoek Rock Dump for possible depletions. An additional site visit by Mr Engelmann was conducted on 10 April 2019 to review the close-out procedures associated with the protracted preceding drilling programme. The most recent site visit by Mr Uwe Engelmann was on 21 January 2020 to investigate the additional waste rock dumps for which the historical data was supplied by Mr Phil Bentley.</p>
If no site visits have been undertaken indicate why this is the case.	Not applicable – refer to above.

SECTION 3: ESTIMATION AND REPORTING OF MINERAL RESOURCES

Detail

	If no site visits have been undertaken indicate why this is the case.	Not applicable – refer to above.																																																													
Geological interpretation	Confidence in (or conversely, the uncertainty of) the geological interpretation of the mineral deposit.	<p>Four types of digital 3D geological models were created in Datamine Studio 3™ and Datamine Studio RM™ for the different types of orebodies within the TGM Projects.</p> <p>The four types of geological models relate to the type of orebodies encountered and include:-</p> <ul style="list-style-type: none"> • Sub-vertical discordant (cross-reef) reef models • Sub-horizontal concordant (and leader) reef models • Topographical surficial reef models • Topographical TSF models <p>The table below presents each of the four types of geological model and the projects that they were applied to:</p> <table border="1"> <thead> <tr> <th>Geological Model Type</th><th>Project Area</th><th>Reef</th></tr> </thead> <tbody> <tr> <td>Sub-vertical discordant (cross-reef) reef models</td><td>Rietfontein</td><td>Rietfontein</td></tr> <tr> <td rowspan="18">Sub-horizontal concordant (and leader) reef models</td><td>Beta (3D)</td><td>Beta</td></tr> <tr> <td rowspan="2">Frankfort (2D)</td><td>Bevetts</td></tr> <tr> <td>Theta</td></tr> <tr> <td>CDM (2D)</td><td>Rho</td></tr> <tr> <td>Olifantsgeraamte (2D)</td><td>Olifantsgeraamte</td></tr> <tr> <td rowspan="2">Vaalhoek (3D)</td><td>Vaalhoek</td></tr> <tr> <td>Thelma Leaders</td></tr> <tr> <td>Glynn's Lydenburg (3D)</td><td>Glynn's</td></tr> <tr> <td rowspan="6">Theta Project (Theta Hill, Browns Hill & Iota section of Columbia Hill) (3D)</td><td>Shale Reefs</td></tr> <tr> <td>Bevetts</td></tr> <tr> <td>Upper Rho</td></tr> <tr> <td>Lower Rho</td></tr> <tr> <td>Upper Theta</td></tr> <tr> <td>Lower Theta</td></tr> <tr> <td rowspan="4">Columbia Hill (3D)</td><td>Beta</td></tr> <tr> <td>Rho</td></tr> <tr> <td>Shale</td></tr> <tr> <td>Shale Leaders</td></tr> <tr> <td rowspan="4">Topographical surficial reef models</td><td>Hermansburg</td><td>Eluvial</td></tr> <tr> <td>DG1</td><td>Eluvial</td></tr> <tr> <td>DG2</td><td>Eluvial</td></tr> <tr> <td>DG5</td><td>Eluvial</td></tr> <tr> <td rowspan="9">Topographical TSF models</td><td>Glynn's Lydenburg</td><td>Tailings</td></tr> <tr> <td>Blyde 1</td><td>Tailings</td></tr> <tr> <td>Blyde 2</td><td>Tailings</td></tr> <tr> <td>Blyde 3</td><td>Tailings</td></tr> <tr> <td>Blyde 4</td><td>Tailings</td></tr> <tr> <td>Blyde 5</td><td>Tailings</td></tr> <tr> <td>Blyde 3a</td><td>Tailings</td></tr> <tr> <td>Vaalhoek</td><td>Rock Dump</td></tr> <tr> <td>South East (DGs), Peach Tree, Ponieskrantz and Dukes Clewer</td><td>Rock Dump (manual)</td></tr> </tbody> </table> <p>The geological reef wireframes for the Concordant and Discordant mineralised zones for all the digital geological models were constructed by Minxcon geologists and are based upon mine development plans and historical surveyed peg files (honouring the on-reef development) provided by TGM. Where this information did not exist, Minxcon digitised the development, stoping outlines, pillars, chip sample data, geological mapping and interpretation data (where available) and survey pegs from digital scans of historical mine survey and sampling plans. Drillholes, survey pegs and thickness modelling were utilised to model the stacked concordant reefs for the Theta Project. The eluvial deposits and TSF models were also constructed by Minxcon geologists and are based upon surveyed contour lines (in the case of the TSFs) and drillhole collars. In the case of the eluvial deposits, topographical contours in conjunction with drillhole collars, were utilised to generate the geological and geographical 3D limits to the geological wireframe models.</p>	Geological Model Type	Project Area	Reef	Sub-vertical discordant (cross-reef) reef models	Rietfontein	Rietfontein	Sub-horizontal concordant (and leader) reef models	Beta (3D)	Beta	Frankfort (2D)	Bevetts	Theta	CDM (2D)	Rho	Olifantsgeraamte (2D)	Olifantsgeraamte	Vaalhoek (3D)	Vaalhoek	Thelma Leaders	Glynn's Lydenburg (3D)	Glynn's	Theta Project (Theta Hill, Browns Hill & Iota section of Columbia Hill) (3D)	Shale Reefs	Bevetts	Upper Rho	Lower Rho	Upper Theta	Lower Theta	Columbia Hill (3D)	Beta	Rho	Shale	Shale Leaders	Topographical surficial reef models	Hermansburg	Eluvial	DG1	Eluvial	DG2	Eluvial	DG5	Eluvial	Topographical TSF models	Glynn's Lydenburg	Tailings	Blyde 1	Tailings	Blyde 2	Tailings	Blyde 3	Tailings	Blyde 4	Tailings	Blyde 5	Tailings	Blyde 3a	Tailings	Vaalhoek	Rock Dump	South East (DGs), Peach Tree, Ponieskrantz and Dukes Clewer	Rock Dump (manual)
Geological Model Type	Project Area	Reef																																																													
Sub-vertical discordant (cross-reef) reef models	Rietfontein	Rietfontein																																																													
Sub-horizontal concordant (and leader) reef models	Beta (3D)	Beta																																																													
	Frankfort (2D)	Bevetts																																																													
		Theta																																																													
	CDM (2D)	Rho																																																													
	Olifantsgeraamte (2D)	Olifantsgeraamte																																																													
	Vaalhoek (3D)	Vaalhoek																																																													
		Thelma Leaders																																																													
	Glynn's Lydenburg (3D)	Glynn's																																																													
	Theta Project (Theta Hill, Browns Hill & Iota section of Columbia Hill) (3D)	Shale Reefs																																																													
		Bevetts																																																													
		Upper Rho																																																													
		Lower Rho																																																													
		Upper Theta																																																													
		Lower Theta																																																													
	Columbia Hill (3D)	Beta																																																													
		Rho																																																													
		Shale																																																													
		Shale Leaders																																																													
Topographical surficial reef models	Hermansburg	Eluvial																																																													
	DG1	Eluvial																																																													
	DG2	Eluvial																																																													
	DG5	Eluvial																																																													
Topographical TSF models	Glynn's Lydenburg	Tailings																																																													
	Blyde 1	Tailings																																																													
	Blyde 2	Tailings																																																													
	Blyde 3	Tailings																																																													
	Blyde 4	Tailings																																																													
	Blyde 5	Tailings																																																													
	Blyde 3a	Tailings																																																													
	Vaalhoek	Rock Dump																																																													
	South East (DGs), Peach Tree, Ponieskrantz and Dukes Clewer	Rock Dump (manual)																																																													

		Minxcon is of the view that the confidence in the geological wireframes is such that it supports the relevant Mineral Resource categorisation currently utilised in the Mineral Resource estimate.																																																																																																																																																																																																
	Nature of the data used and of any assumptions made.	Scanned plans were digitised to generate development strings. These were co-ordinated and repositioned relative to underground plans and survey pegs. Geological plans were also used in conjunction with limited underground geological mapping, underground survey pegs in conjunction with historical and new drillholes were used in the generation of the underground and open-pit project geological models.																																																																																																																																																																																																
	The effect, if any, of alternative interpretations on Mineral Resource estimation.	<p>The geological interpretation of the Sabie-Pilgrims Rest Goldfield (as discussed in the geology section) has not been re-interpreted but what Minxcon has undertaken is a process of collating, capturing and digitising the historical datasets (chip samples, drillhole intersections and historical plans into the electronic environment (GIS and Datamine) to assist in re-investigating the undiscovered potential at the different mines and re-estimation of Mineral Resources if there is potential. Due to the quality and volume of drilling conducted on the Theta Project during 2017-2019, Minxcon was able to generate a lithological model for the first time, which assisted greatly in correctly identifying and correlating individual reefs. In addition, the lithological modelling has played a significant role in the Mineral Reserving process associated with the Theta Project. The surficial or eluvial deposits utilised topographical control as opposed to geological control.</p> <p>The Mineral Resource estimation has been restricted to the hard boundaries defined in the geological interpretation in the form of faulting and outcrop lines. For Rietfontein, a maximum depth below surface of 440 m restricts the depth extension.</p>																																																																																																																																																																																																
	The use of geology in guiding and controlling Mineral Resource estimation.	The geological reef wireframes for the various underground projects were constructed by a Minxcon geologist and are based upon mine development plans and historical surveyed peg files (honouring the on-reef development) provided by TGM. The resultant geological wireframes were then utilised as a closed volume to constrain the volume and spatial estimate of the Mineral Resources. Geological structures were constructed and utilised as hard boundaries for the purposes of Mineral Resource estimation. Due to the quality and volume of drilling conducted on the Theta Project during 2017-2019, Minxcon was able to generate a lithological model for the first time, which assisted greatly in correctly identifying and correlating individual reefs. In addition, the lithological modelling has played a significant role in the Mineral Reserving process associated with the Theta Project. The surficial or eluvial deposits utilised topographical control as opposed to geological control.																																																																																																																																																																																																
	The factors affecting continuity both of grade and geology.	The Mineral Resource estimation has been restricted to the hard boundaries defined in the geological interpretation in the form of faulting and outcrop lines. With regards Rietfontein a maximum depth below surface of 440 m restricts the depth extension.																																																																																																																																																																																																
Dimensions	The extent and variability of the Mineral Resource expressed as length (along strike or otherwise), plan width, and depth below surface to the upper and lower limits of the Mineral Resource.	<p>The block model extents for all the digital project models are shown in the table below. The block models cover all the structures modelled.</p> <table><tr><th rowspan="2">Geological Model Type</th><th rowspan="2">Project Area</th><th rowspan="2">Reef</th><th colspan="3">Block Size</th><th colspan="3">Block Model Dimension</th></tr><tr><th>X (m)</th><th>Y (m)</th><th>Z (m)</th><th>X (m)</th><th>Y (m)</th><th>Z (m)</th></tr><tr><td rowspan="2">Sub-vertical discordant (cross-reef) reef models</td><td rowspan="2">Rietfontein</td><td>Rietfontein</td><td>20</td><td>30</td><td>30</td><td>900</td><td>4020</td><td>1080</td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td rowspan="16">Sub-horizontal concordant (and leader) reef models</td><td rowspan="2">Beta</td><td>Beta</td><td>50</td><td>50</td><td>10</td><td>4350</td><td>4550</td><td>10</td></tr><tr><td>Frankfort</td><td>20</td><td>20</td><td>10</td><td>2100</td><td>1580</td><td>10</td></tr><tr><td rowspan="2">Clewer, Dukes Hill & Morgenzon</td><td>Rho</td><td>50</td><td>50</td><td>10</td><td>3100</td><td>7100</td><td>10</td></tr><tr><td>Olifantsgeraa mte</td><td>20</td><td>20</td><td>1</td><td>800</td><td>1000</td><td>1</td></tr><tr><td rowspan="2">Vaalhoek</td><td>Vaalhoek</td><td>20</td><td>20</td><td>10</td><td>2500</td><td>4380</td><td>10</td></tr><tr><td>Thelma Leaders</td><td>20</td><td>20</td><td>10</td><td>2500</td><td>4380</td><td>10</td></tr><tr><td rowspan="5">Theta Hill & Browns Hill</td><td>Beta</td><td>20</td><td>20</td><td>5</td><td>4000</td><td>3000</td><td>600</td></tr><tr><td>Lower Theta</td><td>20</td><td>20</td><td>5</td><td>4000</td><td>3000</td><td>600</td></tr><tr><td>Upper Theta</td><td>20</td><td>20</td><td>5</td><td>4000</td><td>3000</td><td>600</td></tr><tr><td>Bevetts</td><td>20</td><td>20</td><td>5</td><td>4000</td><td>3000</td><td>600</td></tr><tr><td>Shales</td><td>20</td><td>20</td><td>5</td><td>4000</td><td>3000</td><td>600</td></tr><tr><td rowspan="4">Iota section of Columbia Hill</td><td>Rho Upper</td><td>20</td><td>20</td><td>1</td><td>1140</td><td>1600</td><td>1820</td></tr><tr><td>Rho Lower</td><td>20</td><td>20</td><td>1</td><td>1140</td><td>1600</td><td>1820</td></tr><tr><td>Bevetts</td><td>20</td><td>20</td><td>1</td><td>1140</td><td>1600</td><td>1820</td></tr><tr><td>Upper Theta</td><td>20</td><td>20</td><td>1</td><td>1140</td><td>1600</td><td>1820</td></tr><tr><td>Glynn's Lydenburg</td><td>Glynn's</td><td>20</td><td>20</td><td>10</td><td>7840</td><td>7440</td><td>10</td></tr><tr><td rowspan="3">Topographical surficial reef models</td><td>Hermansburg</td><td>Eluvial</td><td>20</td><td>20</td><td>3</td><td>240</td><td>360</td><td>87</td></tr><tr><td>DG1</td><td>Eluvial</td><td>20</td><td>20</td><td>3</td><td>292</td><td>432</td><td>103</td></tr><tr><td>DG2</td><td>Eluvial</td><td>20</td><td>20</td><td>3</td><td>58</td><td>560</td><td>213</td></tr><tr><td rowspan="2">Topographical TSF models</td><td>Glynn's Lydenburg</td><td>Tailings</td><td>25</td><td>25</td><td>3</td><td>360</td><td>485</td><td>19</td></tr><tr><td>Blyde 1</td><td>Tailings</td><td>25</td><td>25</td><td>3</td><td>340</td><td>260</td><td>20</td></tr></table>	Geological Model Type	Project Area	Reef	Block Size			Block Model Dimension			X (m)	Y (m)	Z (m)	X (m)	Y (m)	Z (m)	Sub-vertical discordant (cross-reef) reef models	Rietfontein	Rietfontein	20	30	30	900	4020	1080								Sub-horizontal concordant (and leader) reef models	Beta	Beta	50	50	10	4350	4550	10	Frankfort	20	20	10	2100	1580	10	Clewer, Dukes Hill & Morgenzon	Rho	50	50	10	3100	7100	10	Olifantsgeraa mte	20	20	1	800	1000	1	Vaalhoek	Vaalhoek	20	20	10	2500	4380	10	Thelma Leaders	20	20	10	2500	4380	10	Theta Hill & Browns Hill	Beta	20	20	5	4000	3000	600	Lower Theta	20	20	5	4000	3000	600	Upper Theta	20	20	5	4000	3000	600	Bevetts	20	20	5	4000	3000	600	Shales	20	20	5	4000	3000	600	Iota section of Columbia Hill	Rho Upper	20	20	1	1140	1600	1820	Rho Lower	20	20	1	1140	1600	1820	Bevetts	20	20	1	1140	1600	1820	Upper Theta	20	20	1	1140	1600	1820	Glynn's Lydenburg	Glynn's	20	20	10	7840	7440	10	Topographical surficial reef models	Hermansburg	Eluvial	20	20	3	240	360	87	DG1	Eluvial	20	20	3	292	432	103	DG2	Eluvial	20	20	3	58	560	213	Topographical TSF models	Glynn's Lydenburg	Tailings	25	25	3	360	485	19	Blyde 1	Tailings	25	25	3	340	260	20
		Geological Model Type				Project Area	Reef	Block Size			Block Model Dimension																																																																																																																																																																																							
X (m)	Y (m)		Z (m)	X (m)	Y (m)			Z (m)																																																																																																																																																																																										
Sub-vertical discordant (cross-reef) reef models	Rietfontein	Rietfontein	20	30	30	900	4020	1080																																																																																																																																																																																										
Sub-horizontal concordant (and leader) reef models	Beta	Beta	50	50	10	4350	4550	10																																																																																																																																																																																										
		Frankfort	20	20	10	2100	1580	10																																																																																																																																																																																										
	Clewer, Dukes Hill & Morgenzon	Rho	50	50	10	3100	7100	10																																																																																																																																																																																										
		Olifantsgeraa mte	20	20	1	800	1000	1																																																																																																																																																																																										
	Vaalhoek	Vaalhoek	20	20	10	2500	4380	10																																																																																																																																																																																										
		Thelma Leaders	20	20	10	2500	4380	10																																																																																																																																																																																										
	Theta Hill & Browns Hill	Beta	20	20	5	4000	3000	600																																																																																																																																																																																										
		Lower Theta	20	20	5	4000	3000	600																																																																																																																																																																																										
		Upper Theta	20	20	5	4000	3000	600																																																																																																																																																																																										
		Bevetts	20	20	5	4000	3000	600																																																																																																																																																																																										
		Shales	20	20	5	4000	3000	600																																																																																																																																																																																										
	Iota section of Columbia Hill	Rho Upper	20	20	1	1140	1600	1820																																																																																																																																																																																										
		Rho Lower	20	20	1	1140	1600	1820																																																																																																																																																																																										
		Bevetts	20	20	1	1140	1600	1820																																																																																																																																																																																										
		Upper Theta	20	20	1	1140	1600	1820																																																																																																																																																																																										
	Glynn's Lydenburg	Glynn's	20	20	10	7840	7440	10																																																																																																																																																																																										
Topographical surficial reef models	Hermansburg	Eluvial	20	20	3	240	360	87																																																																																																																																																																																										
	DG1	Eluvial	20	20	3	292	432	103																																																																																																																																																																																										
	DG2	Eluvial	20	20	3	58	560	213																																																																																																																																																																																										
Topographical TSF models	Glynn's Lydenburg	Tailings	25	25	3	360	485	19																																																																																																																																																																																										
	Blyde 1	Tailings	25	25	3	340	260	20																																																																																																																																																																																										

		<table><tr><td rowspan="11"></td><td>Blyde 2</td><td>Tailings</td><td>25</td><td>25</td><td>3</td><td>156</td><td>172</td><td>20</td></tr><tr><td>Blyde 3</td><td>Tailings</td><td>25</td><td>25</td><td>3</td><td>155</td><td>190</td><td>23</td></tr><tr><td>Blyde 4</td><td>Tailings</td><td>25</td><td>25</td><td>3</td><td>130</td><td>145</td><td>12</td></tr><tr><td>Blyde 5</td><td>Tailings</td><td>25</td><td>25</td><td>3</td><td>95</td><td>60</td><td>12</td></tr><tr><td>Blyde 3a</td><td>Tailings</td><td>25</td><td>25</td><td>3</td><td>120</td><td>135</td><td>7</td></tr><tr><td>TGM Plant</td><td>Tailings</td><td>10</td><td>10</td><td>1.5</td><td>720</td><td>450</td><td>51</td></tr><tr><td>Vaalhoek</td><td>Rock Dump</td><td>10</td><td>10</td><td>1</td><td>280</td><td>300</td><td>40</td></tr><tr><td>South East (DGs)</td><td>Rock Dump</td><td>N/A</td><td>N/A</td><td>N/A</td><td>N/A</td><td>N/A</td><td>N/A</td></tr><tr><td>Peach Tree</td><td>Rock Dump</td><td>N/A</td><td>N/A</td><td>N/A</td><td>N/A</td><td>N/A</td><td>N/A</td></tr><tr><td>Ponieskrantz</td><td>Rock Dump</td><td>N/A</td><td>N/A</td><td>N/A</td><td>N/A</td><td>N/A</td><td>N/A</td></tr><tr><td>Dukes Clewer</td><td>Rock Dump</td><td>N/A</td><td>N/A</td><td>N/A</td><td>N/A</td><td>N/A</td><td>N/A</td></tr><tr><td rowspan="3">Block Plans and/ or Block Listings</td><td>Ponieskrantz*</td><td>Portuguese</td><td>N/A</td><td>N/A</td><td>N/A</td><td>N/A</td><td>N/A</td><td>N/A</td></tr><tr><td>Frankfort Theta*</td><td>Theta</td><td>N/A</td><td>N/A</td><td>N/A</td><td>N/A</td><td>N/A</td><td>N/A</td></tr><tr><td>Nestor*</td><td>Sandstone</td><td>N/A</td><td>N/A</td><td>N/A</td><td>N/A</td><td>N/A</td><td>N/A</td></tr></table> <p>Note: * These historical mines have not been converted yet and are still manual ore resource block lists.</p>		Blyde 2	Tailings	25	25	3	156	172	20	Blyde 3	Tailings	25	25	3	155	190	23	Blyde 4	Tailings	25	25	3	130	145	12	Blyde 5	Tailings	25	25	3	95	60	12	Blyde 3a	Tailings	25	25	3	120	135	7	TGM Plant	Tailings	10	10	1.5	720	450	51	Vaalhoek	Rock Dump	10	10	1	280	300	40	South East (DGs)	Rock Dump	N/A	N/A	N/A	N/A	N/A	N/A	Peach Tree	Rock Dump	N/A	N/A	N/A	N/A	N/A	N/A	Ponieskrantz	Rock Dump	N/A	N/A	N/A	N/A	N/A	N/A	Dukes Clewer	Rock Dump	N/A	N/A	N/A	N/A	N/A	N/A	Block Plans and/ or Block Listings	Ponieskrantz*	Portuguese	N/A	N/A	N/A	N/A	N/A	N/A	Frankfort Theta*	Theta	N/A	N/A	N/A	N/A	N/A	N/A	Nestor*	Sandstone	N/A	N/A	N/A	N/A	N/A	N/A																																																																																																																																																		
	Blyde 2	Tailings		25	25	3	156	172	20																																																																																																																																																																																																																																																													
	Blyde 3	Tailings		25	25	3	155	190	23																																																																																																																																																																																																																																																													
	Blyde 4	Tailings		25	25	3	130	145	12																																																																																																																																																																																																																																																													
	Blyde 5	Tailings		25	25	3	95	60	12																																																																																																																																																																																																																																																													
	Blyde 3a	Tailings		25	25	3	120	135	7																																																																																																																																																																																																																																																													
	TGM Plant	Tailings		10	10	1.5	720	450	51																																																																																																																																																																																																																																																													
	Vaalhoek	Rock Dump		10	10	1	280	300	40																																																																																																																																																																																																																																																													
	South East (DGs)	Rock Dump		N/A	N/A	N/A	N/A	N/A	N/A																																																																																																																																																																																																																																																													
	Peach Tree	Rock Dump		N/A	N/A	N/A	N/A	N/A	N/A																																																																																																																																																																																																																																																													
	Ponieskrantz	Rock Dump		N/A	N/A	N/A	N/A	N/A	N/A																																																																																																																																																																																																																																																													
	Dukes Clewer	Rock Dump	N/A	N/A	N/A	N/A	N/A	N/A																																																																																																																																																																																																																																																														
Block Plans and/ or Block Listings	Ponieskrantz*	Portuguese	N/A	N/A	N/A	N/A	N/A	N/A																																																																																																																																																																																																																																																														
	Frankfort Theta*	Theta	N/A	N/A	N/A	N/A	N/A	N/A																																																																																																																																																																																																																																																														
	Nestor*	Sandstone	N/A	N/A	N/A	N/A	N/A	N/A																																																																																																																																																																																																																																																														
Estimation and modelling techniques	The nature and appropriateness of the estimation technique(s) applied and key assumptions, including treatment of extreme grade values, domaining, interpolation parameters and maximum distance of extrapolation from data points. If a computer assisted estimation method was chosen include a description of computer software and parameters used.	Estimations were carried out utilising Ordinary Kriging for the latest estimations, with the exception of the TGM Plant tailings where Inverse distance squared was seen as most appropriate. The table shows the different estimations techniques per project and the number of domains used. Domains were based on data type available and structural boundaries. The search parameters informed by the variography for the various areas are presented in the table below with the minimum and maximum number of samples used in the estimation.																																																																																																																																																																																																																																																																				
		<table><tr><th rowspan="2">Project Area</th><th rowspan="2">Reef</th><th colspan="2">Vgram Range</th><th colspan="2">Est no Samples</th><th rowspan="2">Type Estimation</th></tr><tr><th>Min</th><th>Max</th><th>Min</th><th>Max</th></tr><tr><td>Rietfontein</td><td>Rietfontein</td><td>40</td><td>120</td><td>5</td><td>15</td><td>Ordinary Kriging</td></tr><tr><td>Beta</td><td>Beta</td><td>40</td><td>297</td><td>5</td><td>20</td><td>Ordinary Kriging</td></tr><tr><td>Frankfort</td><td>Bevetts</td><td>115</td><td>120</td><td>3</td><td>30</td><td>Ordinary Kriging</td></tr><tr><td>CDM</td><td>Rho</td><td>383</td><td>583</td><td>10</td><td>25</td><td>Ordinary Kriging</td></tr><tr><td>Olifantsgeraamte</td><td>Olifantsgeraamte</td><td></td><td></td><td></td><td></td><td>Ordinary Kriging</td></tr><tr><td rowspan="2">Vaalhoek</td><td>Vaalhoek</td><td>68.9</td><td>174.8</td><td>4</td><td>20</td><td>Ordinary Kriging</td></tr><tr><td>Thelma Leaders</td><td>86.7</td><td>96.5</td><td>4</td><td>20</td><td>Ordinary Kriging</td></tr><tr><td rowspan="5">Theta Hill & Browns Hill</td><td>Beta</td><td>90.3</td><td>90.3</td><td>3</td><td>15</td><td>Ordinary Kriging</td></tr><tr><td>Lower Theta</td><td>99.7</td><td>99.7</td><td>3</td><td>15</td><td>Ordinary Kriging</td></tr><tr><td>Upper Theta</td><td>10.4</td><td>10.4</td><td>3</td><td>15</td><td>Ordinary Kriging</td></tr><tr><td>Bevetts</td><td>89.5</td><td>89.5</td><td>3</td><td>15</td><td>Ordinary Kriging</td></tr><tr><td>Shale</td><td>79.6</td><td>79.6</td><td>3</td><td>15</td><td>Ordinary Kriging</td></tr><tr><td rowspan="5">Iota section of Columbia Hill</td><td>Upper Theta</td><td>72</td><td>72</td><td>3</td><td>15</td><td>Ordinary Kriging</td></tr><tr><td>Lower Rho</td><td>72</td><td>72</td><td>3</td><td>15</td><td>Ordinary Kriging</td></tr><tr><td>Upper Rho</td><td>126.9</td><td>126.9</td><td>3</td><td>15</td><td>Ordinary Kriging</td></tr><tr><td>Bevetts</td><td>72.2</td><td>72.2</td><td>2</td><td>10</td><td>Ordinary Kriging</td></tr><tr><td>Shale</td><td>72.2</td><td>72.2</td><td>3</td><td>15</td><td>Ordinary Kriging</td></tr><tr><td>Glynn's Lydenburg</td><td>Glynn's</td><td>75</td><td>488.5</td><td>3</td><td>30</td><td>Ordinary Kriging</td></tr><tr><td>Hermansburg</td><td>Eluvial</td><td>25.8</td><td>25.8</td><td>12</td><td>40</td><td>Ordinary Kriging</td></tr><tr><td>DG1</td><td>Eluvial</td><td>122.5</td><td>122.5</td><td>4</td><td>15</td><td>Ordinary Kriging</td></tr><tr><td>DG2</td><td>Eluvial</td><td>85.8</td><td>85.8</td><td>4</td><td>15</td><td>Ordinary Kriging</td></tr><tr><td>Glynn's Lydenburg</td><td>Tailings</td><td>92.3</td><td>195.8</td><td>4</td><td>40</td><td>Ordinary Kriging</td></tr><tr><td>Blyde 1</td><td>Tailings</td><td>31.8</td><td>31.8</td><td>4</td><td>40</td><td>Ordinary Kriging</td></tr><tr><td>Blyde 2</td><td>Tailings</td><td>30.1</td><td>30.1</td><td>4</td><td>40</td><td>Ordinary Kriging</td></tr><tr><td>Blyde 3</td><td>Tailings</td><td>25.1</td><td>25.1</td><td>4</td><td>40</td><td>Ordinary Kriging</td></tr><tr><td>Blyde 4</td><td>Tailings</td><td>30.7</td><td>30.7</td><td>4</td><td>40</td><td>Ordinary Kriging</td></tr><tr><td>Blyde 5</td><td>Tailings</td><td>7.1</td><td>7.1</td><td>4</td><td>40</td><td>Ordinary Kriging</td></tr><tr><td>Blyde 3a</td><td>Tailings</td><td>31.6</td><td>31.6</td><td>4</td><td>40</td><td>Ordinary Kriging</td></tr><tr><td>TGM Plant</td><td>Tailings</td><td>120</td><td>120</td><td>2</td><td>10</td><td>Inverse distance Squared</td></tr><tr><td>Vaalhoek</td><td>Rock Dump</td><td>18.2</td><td>32.9</td><td>2</td><td>40</td><td>Ordinary Kriging</td></tr><tr><td>South East (DGs)</td><td>Rock Dump</td><td></td><td></td><td></td><td></td><td>Manual/Historic</td></tr><tr><td>Peach Tree</td><td>Rock Dump</td><td></td><td></td><td></td><td></td><td>Manual/Historic</td></tr><tr><td>Ponieskrantz</td><td>Rock Dump</td><td></td><td></td><td></td><td></td><td>Manual/Historic</td></tr><tr><td>Dukes Clewer</td><td>Rock Dump</td><td></td><td></td><td></td><td></td><td>Manual/Historic</td></tr><tr><td>Ponieskrantz*</td><td>Portuguese</td><td></td><td></td><td></td><td></td><td>Manual/Historic</td></tr><tr><td>Frankfort Theta*</td><td>Theta</td><td></td><td></td><td></td><td></td><td>Manual/Historic</td></tr><tr><td>Nestor*</td><td>Sandstone</td><td></td><td></td><td></td><td></td><td>Manual/Historic</td></tr></table> <p>Note: * These historical mines have not been converted yet and are still manual ore resource block lists.</p>	Project Area	Reef	Vgram Range		Est no Samples		Type Estimation	Min	Max	Min	Max	Rietfontein	Rietfontein	40	120	5	15	Ordinary Kriging	Beta	Beta	40	297	5	20	Ordinary Kriging	Frankfort	Bevetts	115	120	3	30	Ordinary Kriging	CDM	Rho	383	583	10	25	Ordinary Kriging	Olifantsgeraamte	Olifantsgeraamte					Ordinary Kriging	Vaalhoek	Vaalhoek	68.9	174.8	4	20	Ordinary Kriging	Thelma Leaders	86.7	96.5	4	20	Ordinary Kriging	Theta Hill & Browns Hill	Beta	90.3	90.3	3	15	Ordinary Kriging	Lower Theta	99.7	99.7	3	15	Ordinary Kriging	Upper Theta	10.4	10.4	3	15	Ordinary Kriging	Bevetts	89.5	89.5	3	15	Ordinary Kriging	Shale	79.6	79.6	3	15	Ordinary Kriging	Iota section of Columbia Hill	Upper Theta	72	72	3	15	Ordinary Kriging	Lower Rho	72	72	3	15	Ordinary Kriging	Upper Rho	126.9	126.9	3	15	Ordinary Kriging	Bevetts	72.2	72.2	2	10	Ordinary Kriging	Shale	72.2	72.2	3	15	Ordinary Kriging	Glynn's Lydenburg	Glynn's	75	488.5	3	30	Ordinary Kriging	Hermansburg	Eluvial	25.8	25.8	12	40	Ordinary Kriging	DG1	Eluvial	122.5	122.5	4	15	Ordinary Kriging	DG2	Eluvial	85.8	85.8	4	15	Ordinary Kriging	Glynn's Lydenburg	Tailings	92.3	195.8	4	40	Ordinary Kriging	Blyde 1	Tailings	31.8	31.8	4	40	Ordinary Kriging	Blyde 2	Tailings	30.1	30.1	4	40	Ordinary Kriging	Blyde 3	Tailings	25.1	25.1	4	40	Ordinary Kriging	Blyde 4	Tailings	30.7	30.7	4	40	Ordinary Kriging	Blyde 5	Tailings	7.1	7.1	4	40	Ordinary Kriging	Blyde 3a	Tailings	31.6	31.6	4	40	Ordinary Kriging	TGM Plant	Tailings	120	120	2	10	Inverse distance Squared	Vaalhoek	Rock Dump	18.2	32.9	2	40	Ordinary Kriging	South East (DGs)	Rock Dump					Manual/Historic	Peach Tree	Rock Dump					Manual/Historic	Ponieskrantz	Rock Dump					Manual/Historic	Dukes Clewer	Rock Dump					Manual/Historic	Ponieskrantz*	Portuguese					Manual/Historic	Frankfort Theta*	Theta					Manual/Historic	Nestor*	Sandstone				
	Project Area	Reef			Vgram Range		Est no Samples			Type Estimation																																																																																																																																																																																																																																																												
Min			Max	Min	Max																																																																																																																																																																																																																																																																	
Rietfontein	Rietfontein	40	120	5	15	Ordinary Kriging																																																																																																																																																																																																																																																																
Beta	Beta	40	297	5	20	Ordinary Kriging																																																																																																																																																																																																																																																																
Frankfort	Bevetts	115	120	3	30	Ordinary Kriging																																																																																																																																																																																																																																																																
CDM	Rho	383	583	10	25	Ordinary Kriging																																																																																																																																																																																																																																																																
Olifantsgeraamte	Olifantsgeraamte					Ordinary Kriging																																																																																																																																																																																																																																																																
Vaalhoek	Vaalhoek	68.9	174.8	4	20	Ordinary Kriging																																																																																																																																																																																																																																																																
	Thelma Leaders	86.7	96.5	4	20	Ordinary Kriging																																																																																																																																																																																																																																																																
Theta Hill & Browns Hill	Beta	90.3	90.3	3	15	Ordinary Kriging																																																																																																																																																																																																																																																																
	Lower Theta	99.7	99.7	3	15	Ordinary Kriging																																																																																																																																																																																																																																																																
	Upper Theta	10.4	10.4	3	15	Ordinary Kriging																																																																																																																																																																																																																																																																
	Bevetts	89.5	89.5	3	15	Ordinary Kriging																																																																																																																																																																																																																																																																
	Shale	79.6	79.6	3	15	Ordinary Kriging																																																																																																																																																																																																																																																																
Iota section of Columbia Hill	Upper Theta	72	72	3	15	Ordinary Kriging																																																																																																																																																																																																																																																																
	Lower Rho	72	72	3	15	Ordinary Kriging																																																																																																																																																																																																																																																																
	Upper Rho	126.9	126.9	3	15	Ordinary Kriging																																																																																																																																																																																																																																																																
	Bevetts	72.2	72.2	2	10	Ordinary Kriging																																																																																																																																																																																																																																																																
	Shale	72.2	72.2	3	15	Ordinary Kriging																																																																																																																																																																																																																																																																
Glynn's Lydenburg	Glynn's	75	488.5	3	30	Ordinary Kriging																																																																																																																																																																																																																																																																
Hermansburg	Eluvial	25.8	25.8	12	40	Ordinary Kriging																																																																																																																																																																																																																																																																
DG1	Eluvial	122.5	122.5	4	15	Ordinary Kriging																																																																																																																																																																																																																																																																
DG2	Eluvial	85.8	85.8	4	15	Ordinary Kriging																																																																																																																																																																																																																																																																
Glynn's Lydenburg	Tailings	92.3	195.8	4	40	Ordinary Kriging																																																																																																																																																																																																																																																																
Blyde 1	Tailings	31.8	31.8	4	40	Ordinary Kriging																																																																																																																																																																																																																																																																
Blyde 2	Tailings	30.1	30.1	4	40	Ordinary Kriging																																																																																																																																																																																																																																																																
Blyde 3	Tailings	25.1	25.1	4	40	Ordinary Kriging																																																																																																																																																																																																																																																																
Blyde 4	Tailings	30.7	30.7	4	40	Ordinary Kriging																																																																																																																																																																																																																																																																
Blyde 5	Tailings	7.1	7.1	4	40	Ordinary Kriging																																																																																																																																																																																																																																																																
Blyde 3a	Tailings	31.6	31.6	4	40	Ordinary Kriging																																																																																																																																																																																																																																																																
TGM Plant	Tailings	120	120	2	10	Inverse distance Squared																																																																																																																																																																																																																																																																
Vaalhoek	Rock Dump	18.2	32.9	2	40	Ordinary Kriging																																																																																																																																																																																																																																																																
South East (DGs)	Rock Dump					Manual/Historic																																																																																																																																																																																																																																																																
Peach Tree	Rock Dump					Manual/Historic																																																																																																																																																																																																																																																																
Ponieskrantz	Rock Dump					Manual/Historic																																																																																																																																																																																																																																																																
Dukes Clewer	Rock Dump					Manual/Historic																																																																																																																																																																																																																																																																
Ponieskrantz*	Portuguese					Manual/Historic																																																																																																																																																																																																																																																																
Frankfort Theta*	Theta					Manual/Historic																																																																																																																																																																																																																																																																
Nestor*	Sandstone					Manual/Historic																																																																																																																																																																																																																																																																
	The availability of check estimates, previous	<table><tr><th rowspan="2">Project Area</th><th rowspan="2">Reef</th><th>Historic Estimate Available</th></tr><tr><th>Yes/No</th></tr><tr><td>Rietfontein</td><td>Rietfontein</td><td>Yes</td></tr><tr><td>Beta</td><td>Beta</td><td>Yes</td></tr></table>	Project Area	Reef	Historic Estimate Available	Yes/No	Rietfontein	Rietfontein	Yes	Beta	Beta	Yes																																																																																																																																																																																																																																																										
Project Area	Reef	Historic Estimate Available																																																																																																																																																																																																																																																																				
		Yes/No																																																																																																																																																																																																																																																																				
Rietfontein	Rietfontein	Yes																																																																																																																																																																																																																																																																				
Beta	Beta	Yes																																																																																																																																																																																																																																																																				

estimates and/or mine production records and whether the Mineral Resource estimate takes appropriate account of such data.	Frankfort	Bevetts	Yes																																														
	Clewer, Dukes Hill & Morgenzon	Rho	No – not a combined resource																																														
	Olifantsgeraamte	Olifantsgeraamte	Yes																																														
	Vaalhoek	Vaalhoek	No – not a complete electronic resource																																														
		Thelma Leaders	No – not a complete electronic resource																																														
	Glynn's Lydenburg	Glynn's	No – not a complete electronic resource																																														
	Theta Hill & Browns Hill	Beta	No																																														
		Lower Theta	No																																														
		Upper Theta	No																																														
		Bevetts	No																																														
		Shale	No																																														
	Iota section of Columbia Hill	Upper Theta	No																																														
		Lower Rho	No																																														
		Upper Rho	No																																														
		Bevetts	No																																														
	Hermansburg	Eluvial	Yes																																														
	DG1	Eluvial	Yes																																														
	DG2	Eluvial	Yes																																														
	Glynn's Lydenburg	Tailings	Yes																																														
	Blyde 1	Tailings	Yes																																														
	Blyde 2	Tailings	Yes																																														
	Blyde 3	Tailings	Yes																																														
	Blyde 4	Tailings	Yes																																														
	Blyde 5	Tailings	Yes																																														
	Blyde 3a	Tailings	Yes																																														
	TGM Plant	Tailings	No – not from drill sampling																																														
	Vaalhoek	Rock Dump	Yes																																														
	South East (DGs)	Rock Dump	Yes																																														
	Peach Tree	Rock Dump	Yes																																														
	Ponieskrantz	Rock Dump	Yes																																														
	Dukes Clewer	Rock Dump	Yes																																														
	Ponieskrantz*	Portuguese	No																																														
	Frankfort Theta*	Theta	No																																														
	Nestor*	Sandstone	No																																														
	Note: * These historical mines have not been converted yet and are still manual ore resource block lists.																																																
The assumptions made regarding recovery of by-products.	No investigation has been conducted with regards secondary mineralisation or correlation between pyrite and gold.																																																
Estimation of deleterious elements or other non-grade variables of economic significance (e.g. sulphur for acid mine drainage characterisation).	No estimates pertaining to deleterious elements or other non-grade variables of economic significance (e.g. sulphur for acid mine drainage characterisation) have been conducted.																																																
In the case of block model interpolation, the block size in relation to the average sample spacing and the search employed.	<table><tr><th rowspan="2">Geologic al Model Type</th><th rowspan="2">Project Area</th><th rowspan="2">Reef</th><th colspan="3">Block Size</th><th colspan="3">Block Model Dimension</th><th rowspan="2">Sample Spacing</th></tr><tr><th>X</th><th>Y</th><th>Z</th><th>X</th><th>Y</th><th>Z</th></tr><tr><td>Sub-vertical discordant (cross-reef) reef models</td><td>Rietfontein</td><td>Rietfontein</td><td>20</td><td>30</td><td>30</td><td>900</td><td>4020</td><td>1080</td><td>3-5 m</td></tr><tr><td rowspan="2">Sub-horizontal concordance</td><td>Beta</td><td>Beta</td><td>50</td><td>50</td><td>10</td><td>4350</td><td>4550</td><td>10</td><td>3-5 m</td></tr><tr><td>Frankfort</td><td>Bevetts</td><td>20</td><td>20</td><td>10</td><td>2100</td><td>1580</td><td>10</td><td>3-5 m</td></tr></table>				Geologic al Model Type	Project Area	Reef	Block Size			Block Model Dimension			Sample Spacing	X	Y	Z	X	Y	Z	Sub-vertical discordant (cross-reef) reef models	Rietfontein	Rietfontein	20	30	30	900	4020	1080	3-5 m	Sub-horizontal concordance	Beta	Beta	50	50	10	4350	4550	10	3-5 m	Frankfort	Bevetts	20	20	10	2100	1580	10	3-5 m
Geologic al Model Type	Project Area	Reef	Block Size					Block Model Dimension			Sample Spacing																																						
			X	Y	Z	X	Y	Z																																									
Sub-vertical discordant (cross-reef) reef models	Rietfontein	Rietfontein	20	30	30	900	4020	1080	3-5 m																																								
Sub-horizontal concordance	Beta	Beta	50	50	10	4350	4550	10	3-5 m																																								
	Frankfort	Bevetts	20	20	10	2100	1580	10	3-5 m																																								

		nt (and leader) reef models	Clewer, Dukes Hill & Morgen zon	Rho	50	50	10	3100	7100	10	3-5 m	
			Olifants geraamte	Olifantsge raamte	20	20	1	800	1000	1	3-5 m	
			Vaalhoe k	Vaalhoek	20	20	10	2500	4380	10	3-5 m	
				Thelma Leaders	20	20	10	2500	4380	10	3-5 m	
			Glynn's Lydenburg	Glynn's	20	20	10	7840	7440	10	3-5 m	
			Theta Hill & Browns Hill	Beta	20	20	5	4000	3000	600	3-100 m	
				Lower Theta	20	20	5	4000	3000	600	3-100 m	
				Upper Theta	20	20	5	4000	3000	600	50-100 m	
				Bevetts	20	20	5	4000	3000	600	50-100 m	
				Shales	20	20	5	4000	3000	600	50-100 m	
			Iota section of Columbi a Hill	Rho Upper	20	20	1	1140	1600	1820	3-75 m	
				Rho Lower	20	20	1	1140	1600	1820	50-100 m	
				Bevetts	20	20	1	1140	1600	1820	50-100 m	
				Upper Theta	20	20	1	1140	1600	1820	50-100 m	
			Topograp hical surficial reef models	Herman sburg	Eluvial	20	20	3	240	360	87	25 m
				DG1	Eluvial	20	20	3	292	432	103	25 m
				DG2	Eluvial	20	20	3	58	560	213	25 m
			Topograp hical TSF models	Glynn's Lydenburg	Tailings	25	25	3	360	485	19	25 m
				Blyde 1	Tailings	25	25	3	340	260	20	25 m
				Blyde 2	Tailings	25	25	3	156	172	20	25 m
				Blyde 3	Tailings	25	25	3	155	190	23	25 m
				Blyde 4	Tailings	25	25	3	130	145	12	25 m
				Blyde 5	Tailings	25	25	3	95	60	12	25 m
				Blyde 3a	Tailings	25	25	3	120	135	7	25 m
				TGM Plant	Tailings	10	10	1.5	720	450	51	50 m
				Vaalhoe k	Rock Dump	10	10	1	280	300	40	25 m
				South East (DGs)	Rock Dump	N/A	N/A	N/A	N/A	N/A	N/A	
				Peach Tree	Rock Dump	N/A	N/A	N/A	N/A	N/A	N/A	
				Poniesk rantz	Rock Dump	N/A	N/A	N/A	N/A	N/A	N/A	
				Dukes Clewer	Rock Dump	N/A	N/A	N/A	N/A	N/A	N/A	
				Block Plans and/ or Block Listings	Poniesk rantz*	Portuguese	N/A	N/A	N/A	N/A	N/A	N/A
			Frankfo rt Theta*		Theta	N/A	N/A	N/A	N/A	N/A	N/A	
			Nestor*		Sandstone	N/A	N/A	N/A	N/A	N/A	N/A	
			Note: * These historical mines have not been converted yet and are still manual ore resource block lists.									
			The Block Models produced in Datamine Studio RM™ consisting of a cell sizes as shown in the above table. Final estimated models were projected to the reef plan based on the structural interpretation.									
	Any assumptions behind modelling of		No assumptions were made in terms of selective mining units with respect to the cell size selected.									

	selective mining units.																																																																																																																																																																																										
Estimation and modelling techniques (continued)	Any assumptions about correlation between variables.	Grade (Au g/t) and reef width were estimated - no correlation between thickness and grade was found during the statistical analysis, however a cm.g/t value was calculated on a post estimation basis.																																																																																																																																																																																									
	Description of how the geological interpretation was used to control the resource estimates.	The Mineral Resource estimation has been restricted to the hard boundaries encompassed by the geological wireframes.																																																																																																																																																																																									
	Discussion of basis for using or not using grade cutting or capping.	<p>The data sets were capped per domain and the following table indicates the minimum and maximum capping of the upper limits of the data sets. Minxcon utilised 'Cumulative Coefficient of Variation' plots to assist with the capping. Reef widths were capped in the same manner due to anomalies in the sampling thickness and generally occur between the 95th to the 99th percentile. CAE Studio RM™ was utilised for the statistics, geostatistics and block model estimation. Capping ranges as depicted in the table below represent capping range for the various domains per project. These are broken up in detail in the CPR.</p> <table><tr><th rowspan="2">Geological Model Type</th><th rowspan="2">Project Area</th><th rowspan="2">Reef</th><th colspan="2">Capping</th><th rowspan="2">Number of Estimation Samples</th></tr><tr><th>RW (cm)</th><th>Au (g/t)</th></tr><tr><td>Sub-vertical discordant (cross-reef) reef models</td><td>Rietfontein</td><td>Rietfontein</td><td>236</td><td>123.5</td><td>2,262</td></tr><tr><td rowspan="16">Sub-horizontal concordant (and leader) reef models</td><td>Beta</td><td>Beta</td><td>170.0</td><td>300</td><td>4,566</td></tr><tr><td>Frankfort</td><td>Bevetts</td><td>200-281</td><td>46.6-57.5</td><td>4,114</td></tr><tr><td>Clewer, Dukes Hill & Morgenzon</td><td>Rho</td><td>50</td><td>314.5</td><td>24,693</td></tr><tr><td>Olifantsgeraamte</td><td>Olifantsgeraamte</td><td>142</td><td>147.3</td><td>316</td></tr><tr><td rowspan="2">Vaalhoek</td><td>Vaalhoek</td><td>335.3</td><td>411.4</td><td>16,652</td></tr><tr><td>Thelma Leaders</td><td>54 -78</td><td>137-304</td><td>901</td></tr><tr><td>Glynn's Lydenburg</td><td>Glynn's</td><td>105-281</td><td>100-134</td><td>29,444</td></tr><tr><td rowspan="4">Theta Hill & Browns Hill</td><td>Beta</td><td>176</td><td>14.0</td><td>1,673</td></tr><tr><td>Lower Theta</td><td>176</td><td>18.2</td><td>5,609</td></tr><tr><td>Upper Theta</td><td>176</td><td>63.4</td><td>148</td></tr><tr><td>Bevetts</td><td>N/A</td><td>14.0</td><td>155</td></tr><tr><td rowspan="4">Iota section of Columbia Hill</td><td>Shale</td><td>N/A</td><td>4.9</td><td>59</td></tr><tr><td>Upper Theta</td><td>N/A</td><td>9.1</td><td>39</td></tr><tr><td>Lower Rho</td><td>N/A</td><td>23.0</td><td>680</td></tr><tr><td>Upper Rho</td><td>N/A</td><td>212.0</td><td>208</td></tr><tr><td>Bevetts</td><td>N/A</td><td>19.4</td><td>26</td></tr><tr><td rowspan="3">Topographical surficial reef models</td><td>Hermansburg</td><td>Eluvial</td><td>N/A</td><td>67.1</td><td>1,076</td></tr><tr><td>DG1</td><td>Eluvial</td><td>N/A</td><td>8.55</td><td>784</td></tr><tr><td>DG2</td><td>Eluvial</td><td>N/A</td><td>22.5</td><td>234</td></tr><tr><td rowspan="12">Topographical TSF models</td><td>Glynn's Lydenburg</td><td>Tailings</td><td>N/A</td><td>1.8</td><td>793</td></tr><tr><td>Blyde 1</td><td>Tailings</td><td>N/A</td><td>2.2</td><td>288</td></tr><tr><td>Blyde 2</td><td>Tailings</td><td>N/A</td><td>2.1</td><td>176</td></tr><tr><td>Blyde 3</td><td>Tailings</td><td>N/A</td><td>1.0</td><td>179</td></tr><tr><td>Blyde 4</td><td>Tailings</td><td>N/A</td><td>0.9</td><td>104</td></tr><tr><td>Blyde 5</td><td>Tailings</td><td>N/A</td><td>1.0</td><td>40</td></tr><tr><td>Blyde 3a</td><td>Tailings</td><td>N/A</td><td>0.9</td><td>27</td></tr><tr><td>TGM Plant</td><td>Tailings</td><td>N/A</td><td>2.6</td><td>288</td></tr><tr><td>Vaalhoek</td><td>Rock Dump</td><td>N/A</td><td>4.1 -16.1</td><td>80</td></tr><tr><td>South East (DGs)</td><td>Rock Dump</td><td>N/A</td><td>N/A</td><td>N/A</td></tr><tr><td>Peach Tree</td><td>Rock Dump</td><td>N/A</td><td>N/A</td><td>N/A</td></tr><tr><td>Ponieskrantz</td><td>Rock Dump</td><td>N/A</td><td>N/A</td><td>N/A</td></tr><tr><td rowspan="3">Block Plans and/or Block Listings</td><td>Dukes Clewer</td><td>Rock Dump</td><td>N/A</td><td>N/A</td><td>N/A</td></tr><tr><td>Ponieskrantz*</td><td>Portuguese</td><td>N/A</td><td>N/A</td><td>N/A</td></tr><tr><td>Frankfort Theta*</td><td>Theta</td><td>N/A</td><td>N/A</td><td>N/A</td></tr><tr><td></td><td>Nestor*</td><td>Sandstone</td><td>N/A</td><td>N/A</td><td>N/A</td></tr></table> <p>Note: * These historical mines have not been converted yet and are still manual ore resource block lists.</p>	Geological Model Type	Project Area	Reef	Capping		Number of Estimation Samples	RW (cm)	Au (g/t)	Sub-vertical discordant (cross-reef) reef models	Rietfontein	Rietfontein	236	123.5	2,262	Sub-horizontal concordant (and leader) reef models	Beta	Beta	170.0	300	4,566	Frankfort	Bevetts	200-281	46.6-57.5	4,114	Clewer, Dukes Hill & Morgenzon	Rho	50	314.5	24,693	Olifantsgeraamte	Olifantsgeraamte	142	147.3	316	Vaalhoek	Vaalhoek	335.3	411.4	16,652	Thelma Leaders	54 -78	137-304	901	Glynn's Lydenburg	Glynn's	105-281	100-134	29,444	Theta Hill & Browns Hill	Beta	176	14.0	1,673	Lower Theta	176	18.2	5,609	Upper Theta	176	63.4	148	Bevetts	N/A	14.0	155	Iota section of Columbia Hill	Shale	N/A	4.9	59	Upper Theta	N/A	9.1	39	Lower Rho	N/A	23.0	680	Upper Rho	N/A	212.0	208	Bevetts	N/A	19.4	26	Topographical surficial reef models	Hermansburg	Eluvial	N/A	67.1	1,076	DG1	Eluvial	N/A	8.55	784	DG2	Eluvial	N/A	22.5	234	Topographical TSF models	Glynn's Lydenburg	Tailings	N/A	1.8	793	Blyde 1	Tailings	N/A	2.2	288	Blyde 2	Tailings	N/A	2.1	176	Blyde 3	Tailings	N/A	1.0	179	Blyde 4	Tailings	N/A	0.9	104	Blyde 5	Tailings	N/A	1.0	40	Blyde 3a	Tailings	N/A	0.9	27	TGM Plant	Tailings	N/A	2.6	288	Vaalhoek	Rock Dump	N/A	4.1 -16.1	80	South East (DGs)	Rock Dump	N/A	N/A	N/A	Peach Tree	Rock Dump	N/A	N/A	N/A	Ponieskrantz	Rock Dump	N/A	N/A	N/A	Block Plans and/or Block Listings	Dukes Clewer	Rock Dump	N/A	N/A	N/A	Ponieskrantz*	Portuguese	N/A	N/A	N/A	Frankfort Theta*	Theta	N/A	N/A	N/A		Nestor*	Sandstone	N/A	N/A
Geological Model Type	Project Area	Reef				Capping			Number of Estimation Samples																																																																																																																																																																																		
			RW (cm)	Au (g/t)																																																																																																																																																																																							
Sub-vertical discordant (cross-reef) reef models	Rietfontein	Rietfontein	236	123.5	2,262																																																																																																																																																																																						
Sub-horizontal concordant (and leader) reef models	Beta	Beta	170.0	300	4,566																																																																																																																																																																																						
	Frankfort	Bevetts	200-281	46.6-57.5	4,114																																																																																																																																																																																						
	Clewer, Dukes Hill & Morgenzon	Rho	50	314.5	24,693																																																																																																																																																																																						
	Olifantsgeraamte	Olifantsgeraamte	142	147.3	316																																																																																																																																																																																						
	Vaalhoek	Vaalhoek	335.3	411.4	16,652																																																																																																																																																																																						
		Thelma Leaders	54 -78	137-304	901																																																																																																																																																																																						
	Glynn's Lydenburg	Glynn's	105-281	100-134	29,444																																																																																																																																																																																						
	Theta Hill & Browns Hill	Beta	176	14.0	1,673																																																																																																																																																																																						
		Lower Theta	176	18.2	5,609																																																																																																																																																																																						
		Upper Theta	176	63.4	148																																																																																																																																																																																						
		Bevetts	N/A	14.0	155																																																																																																																																																																																						
	Iota section of Columbia Hill	Shale	N/A	4.9	59																																																																																																																																																																																						
		Upper Theta	N/A	9.1	39																																																																																																																																																																																						
		Lower Rho	N/A	23.0	680																																																																																																																																																																																						
		Upper Rho	N/A	212.0	208																																																																																																																																																																																						
	Bevetts	N/A	19.4	26																																																																																																																																																																																							
Topographical surficial reef models	Hermansburg	Eluvial	N/A	67.1	1,076																																																																																																																																																																																						
	DG1	Eluvial	N/A	8.55	784																																																																																																																																																																																						
	DG2	Eluvial	N/A	22.5	234																																																																																																																																																																																						
Topographical TSF models	Glynn's Lydenburg	Tailings	N/A	1.8	793																																																																																																																																																																																						
	Blyde 1	Tailings	N/A	2.2	288																																																																																																																																																																																						
	Blyde 2	Tailings	N/A	2.1	176																																																																																																																																																																																						
	Blyde 3	Tailings	N/A	1.0	179																																																																																																																																																																																						
	Blyde 4	Tailings	N/A	0.9	104																																																																																																																																																																																						
	Blyde 5	Tailings	N/A	1.0	40																																																																																																																																																																																						
	Blyde 3a	Tailings	N/A	0.9	27																																																																																																																																																																																						
	TGM Plant	Tailings	N/A	2.6	288																																																																																																																																																																																						
	Vaalhoek	Rock Dump	N/A	4.1 -16.1	80																																																																																																																																																																																						
	South East (DGs)	Rock Dump	N/A	N/A	N/A																																																																																																																																																																																						
	Peach Tree	Rock Dump	N/A	N/A	N/A																																																																																																																																																																																						
	Ponieskrantz	Rock Dump	N/A	N/A	N/A																																																																																																																																																																																						
Block Plans and/or Block Listings	Dukes Clewer	Rock Dump	N/A	N/A	N/A																																																																																																																																																																																						
	Ponieskrantz*	Portuguese	N/A	N/A	N/A																																																																																																																																																																																						
	Frankfort Theta*	Theta	N/A	N/A	N/A																																																																																																																																																																																						
	Nestor*	Sandstone	N/A	N/A	N/A																																																																																																																																																																																						

	The process of validation, the checking process used, the comparison of model data to drillhole data, and use of reconciliation data if available.	Swath analysis of the current estimated projects were conducted in the east-west and north-south directions in order to check correlations between the block modelled grades and the raw sampled values. Swath analysis shows a good correlation with the sample grade. In addition, correlation between the estimate and the average value of a block was investigated. Historic estimates (eluvials & TSFs and Olifantsgeraamte) were reviewed visually to ensure similar grade trends between drillholes or sampling points and the final block models. In addition, for the TSFs the mean sampled value was compared to the mean estimated value of the block models.																																													
Moisture	Whether the tonnages are estimated on a dry basis or with natural moisture, and the method of determination of the moisture content.	The density is based on a dry rock mass.																																													
Cut-off parameters	The basis of the adopted cut-off grade(s) or quality parameters applied.	<p>The Mineral Resource has been split into underground Mineral Resources, open pit Mineral Resources and tailings dams.</p> <p>The following parameters were used for the declaration and pay limit calculation: Gold price, % MCF, dilution, discount rate, plant recovery factor, mining cost total plant cost. The gold price of USD1,497/oz, is the 90th percentile of the historical real term commodity prices since 1980.</p> <table border="1"> <thead> <tr> <th>Description</th><th>Unit</th><th>Value</th></tr> </thead> <tbody> <tr> <td>Gold Price</td><td>USD/oz</td><td>1,500</td></tr> <tr> <td>% MCF</td><td>%</td><td>90%</td></tr> <tr> <td>Dilution</td><td>%</td><td>0%</td></tr> <tr> <td>Plant Recovery Factor</td><td>%</td><td>90%</td></tr> <tr> <td>Mining Costs</td><td>ZAR/t</td><td>522</td></tr> <tr> <td>Total Plant Cost</td><td>ZAR/t</td><td>472</td></tr> <tr> <td>Total Cost</td><td>ZAR</td><td>994</td></tr> </tbody> </table> <p>For the open pit Mineral Resource cut-off, the following parameters were used.</p> <table border="1"> <thead> <tr> <th>Description</th><th>Unit</th><th>Value</th></tr> </thead> <tbody> <tr> <td>Gold Price</td><td>USD/oz</td><td>1,500</td></tr> <tr> <td>% MCF</td><td>%</td><td>100%</td></tr> <tr> <td>Dilution</td><td>%</td><td>0%</td></tr> <tr> <td>Plant Recovery Factor</td><td>%</td><td>92%</td></tr> <tr> <td>Mining Costs</td><td>ZAR/t</td><td>24</td></tr> <tr> <td>Total Plant Cost</td><td>ZAR/t</td><td>269</td></tr> </tbody> </table> <p>For the tailings Mineral Resource cut-off, the parameters were the same as above except the plant recovery factor which was 50% and the total mining and processing cost of ZAR135/t with a 10% discount.</p> <p>The resultant cut-offs were 160 cm.g/t for the underground (pay limit calculation); 0.5 g/t and 0.35 g/t for the Theta Project (economic cut-off calculation) for the open pit (with in the pit shell using Datamine Maxipit software) and 0.35 g/t for the tailings dam and rock dumps (pay limit calculation).</p>	Description	Unit	Value	Gold Price	USD/oz	1,500	% MCF	%	90%	Dilution	%	0%	Plant Recovery Factor	%	90%	Mining Costs	ZAR/t	522	Total Plant Cost	ZAR/t	472	Total Cost	ZAR	994	Description	Unit	Value	Gold Price	USD/oz	1,500	% MCF	%	100%	Dilution	%	0%	Plant Recovery Factor	%	92%	Mining Costs	ZAR/t	24	Total Plant Cost	ZAR/t	269
Description	Unit	Value																																													
Gold Price	USD/oz	1,500																																													
% MCF	%	90%																																													
Dilution	%	0%																																													
Plant Recovery Factor	%	90%																																													
Mining Costs	ZAR/t	522																																													
Total Plant Cost	ZAR/t	472																																													
Total Cost	ZAR	994																																													
Description	Unit	Value																																													
Gold Price	USD/oz	1,500																																													
% MCF	%	100%																																													
Dilution	%	0%																																													
Plant Recovery Factor	%	92%																																													
Mining Costs	ZAR/t	24																																													
Total Plant Cost	ZAR/t	269																																													
Mining factors or assumptions	Assumptions made regarding possible mining methods, minimum mining	A minimum stoping width of 90 cm was assumed. Where reef width (or channel width) was less than 70 cm, dilution was increased accordingly. Elsewhere, the stoping width was calculated by adding 20 cm dilution to the Mineral Resource Estimation. No dilution was applied to the open pit Mineral Resources, nor the TSF Mineral Resources, with the exception of the new Theta Project where narrow reefs (<100 cm reef thickness) were diluted to 100 cm due to the drilling sample run achieved in the RC drilling programme being at 1 m intervals.																																													

	<p>dimensions and internal (or, if applicable, external) mining dilution. It is always necessary as part of the process of determining reasonable prospects for eventual economic extraction to consider potential mining methods, but the assumptions made regarding mining methods and parameters when estimating Mineral Resources may not always be rigorous. Where this is the case, this should be reported with an explanation of the basis of the mining assumptions made.</p>	
Metallurgical factors or assumptions	<p>The basis for assumptions or predictions regarding metallurgical amenability. It is always necessary as part of the process of determining reasonable prospects for eventual economic extraction to consider potential metallurgical methods, but the assumptions regarding metallurgical</p>	<p>All of the ore will be processed via cyanide leach and carbon adsorption as is done with most gold ores. A different recovery estimate was used for each mine and reef where applicable.</p> <p>The recovery assumed for Beta was 86% as it is known to be a free milling ore with limited preg-robbing characteristics. Frankfort is a double refractory ore, with significant locked gold and preg-robbes. A 69% recovery was assumed. CDM also contains sulphides but historically gave fair recoveries, and 86% was assumed. The Theta Project has a number of reefs and a recovery for each was assumed. Recovery for the Upper Theta, Lower Theta and Beta composites are assumed to be 88.78%, 95.28% and 86.54% respectively. Bevetts, Shale and Rho Reefs were all assumed to give 91.56 % recovery.</p>

	<p>treatment processes and parameters made when reporting Mineral Resources may not always be rigorous. Where this is the case, this should be reported with an explanation of the basis of the metallurgical assumptions made.</p>	
<p>Environmental factors or assumptions</p>	<p>Assumptions made regarding possible waste and process residue disposal options. It is always necessary as part of the process of determining reasonable prospects for eventual economic extraction to consider the potential environmental impacts of the mining and processing operation. While at this stage the determination of potential environmental impacts, particularly for a greenfields project, may not always be well advanced, the status of early consideration of these potential environmental impacts should be</p>	<p>No environmental factors or assumptions were applied to this Mineral Resource estimation.</p>

	<p>reported. Where these aspects have not been considered this should be reported with an explanation of the environmental assumptions made.</p>	
Bulk density	<p>Whether assumed or determined. If assumed, the basis for the assumptions. If determined, the method used, whether wet or dry, the frequency of the measurements, the nature, size and representativeness of the samples.</p>	<p>No historical bulk density measurement data is available besides a tabulated summary table indicating historically applied densities for the various in situ reefs. However, bulk density tests have been carried out for the Theta Project reefs host lithologies. Reef samples suitable for bulk density tests were however limited due to the poor core recovery achieved in the 2017-2019 diamond drilling programme. A density of 3.6 g/cm³ was used for the calculation of in situ underground and open pit hard rock ore tonnes, in line with the value used in previous declarations. A density of 2.84 g/cm³, which is the average density of dolomite, was used for the waste or dilution tonnes. The Rietfontein estimate uses a 2.9 t/m³ based on historical assumptions and estimates.</p> <p>The Theta Project uses a bulk density of 2.75 t/m³ for the estimation in areas where there was new drilling data. The historical 3.6 t/m³ for reef and 2.84 t/m³ for the dolomites were still used in the historical areas as there was no new data. In these areas the diluted reef density is in the region of 3.1 t/m³. The 2.75 t/m³ is based on the field testing of the core samples only as the RC chips could not be used due to the weathered nature and fine material in the samples. 156 density readings were taken on the available reef core of which 27 were not reliable due to high clay (WAD) content and fine material. For the 129 representative core samples the density was 2.69 t/m³ and for the solid core (53 samples) it was 2.78 t/m³. Therefore, a density of 2.75 t/m³ was utilised. More work is required on the density with further drilling campaigns to obtain more readings and a higher level of confidence in the density. The density is one of the reasons that the Mineral Resource categories in the Theta Project are only Indicated and Inferred with no Measured Mineral Resources. Densities were determined utilising the Archimedes principle.</p> <p>Bulk density for the eluvial deposits was assumed at 2.3 t/m³ based on typical unconsolidated material densities.</p> <p>Minxcon used an SG of 1.4 t/m³ for the modelling of all of the historical TSFs, with the exception of the TGM Plant TSF, where SG measurements were conducted utilising the "pipe method". The SG for this TSF was calculated at 1.54 t/m³ from a total of 40 samples taken at various locations all over the TSF. In Minxcon's view this SG may be considered to representative for this TSF.</p>
	<p>The bulk density for bulk material must have been measured by methods that adequately account for void spaces (vugs, porosity, etc.), moisture and differences between rock and alteration zones within the deposit.</p>	<p>The pipe method (as utilised on the TGM Plant TSF) of measuring bulk density is utilised on soft sediments and is conducted in such a manner as to ensure that little to no compaction of the material within the pipe occurs. This serves to preserve the inherent sediment porosity.</p>
	<p>Discuss assumptions for bulk density estimates used in the evaluation process of</p>	<p>No historical bulk density measurement data is available besides a tabulated summary table indicating historically applied densities for the various in situ reefs. However, bulk density tests have been carried out for the Theta Project reefs host lithologies. Reef samples suitable for bulk density tests were however limited due to the poor core recovery achieved in the 2017-2019 diamond drilling programme. A density of 3.6 g/cm³ was used for the calculation of in situ underground and open pit hard rock ore tonnes, in line with the value used in previous declarations. A density of 2.84 g/cm³, which is the average density of dolomite, was used for the waste or dilution tonnes. The Rietfontein estimate uses a 2.9 t/m³ based on historical assumptions and estimates.</p>

	the different materials.	<p>The Theta Project uses a bulk density of 2.75 t/m³ for the estimation in areas where there was new drilling data. The historical 3.6 t/m³ for reef and 2.84 t/m³ for the dolomites were still used in the historical areas as there was no new data. In these areas the diluted reef density is in the region of 3.1 t/m³. The 2.75 t/m³ is based on the field testing of the core samples only as the RC chips could not be used due to the weathered nature and fine material in the samples. 156 density readings were taken on the available reef core of which 27 were not reliable due to high clay (WAD) content and fine material. For the 129 representative core samples the density was 2.69 t/m³ and for the solid core (53 samples) it was 2.78 t/m³. Therefore, a density of 2.75 t/m³ was utilised. More work is required on the density with further drilling campaigns to obtain more readings and a higher level of confidence in the density. The density is one of the reasons that the Mineral Resource categories in the Theta Project are only Indicated and Inferred with no Measured Mineral Resources. Densities were determined utilising the Archimedes principle.</p> <p>Bulk density for the eluvial deposits was assumed at 2.3 t/m³ based on typical unconsolidated material densities.</p> <p>Minxcon used an SG of 1.4 t/m³ for the modelling of all of the historical TSFs, with the exception of the TGM Plant TSF, where SG measurements were conducted utilising the "pipe method". The SG for this TSF was calculated at 1.54 t/m³ from a total of 40 samples taken at various locations all over the TSF. In Minxcon's view this SG may be considered to representative for this TSF.</p>
Classification	The basis for the classification of the Mineral Resources into varying confidence categories.	<p>The Mineral Resource classification for the all the block models is based on a positive kriging efficiency, calculated variogram ranges and number of samples informing the estimation. Where confidence in the historical sampling values or position were low the classification was downgraded to Inferred Mineral Resource.</p> <p>At the Theta Project, the highest Mineral Resource classification applied was Indicated (regardless of data spacing: 1) Historical nature associated with the chip sampling dataset, stretch values and block values and around the historical drillholes. 2) The low availability of detailed bulk density data 3) the low volume of diamond drilling conducted at the Project.</p>
	Whether appropriate account has been taken of all relevant factors (i.e. relative confidence in tonnage/grade estimations, reliability of input data, confidence in continuity of geology and metal values, quality, quantity and distribution of the data).	<p>Mineral Resources were only classified as Indicated and Inferred Mineral Resources in the vast majority of cases due to the age and spacing of the data utilised. Measured Mineral Resources were only identified on a small portion of Frankfort due to the recent nature of some areas of the channel chip sampling data. Minxcon utilised a combination of variogram ranges, spread in confidence limits and minimum number of samples to be utilised in the estimate, in conjunction with geological continuity to assign Mineral Resource categories.</p> <p>At the Theta Project, the highest Mineral Resource classification applied was Indicated (regardless of data spacing: 1) Historical nature associated with the chip sampling dataset, stretch values and block values and around the historical drillholes. 2) The low availability of detailed bulk density data 3) the low volume of diamond drilling conducted at the Project.</p> <p>The additional rock dumps (South East (DGs), Peach Tree, Ponieskrantz and Dukes Clewer) have all been classified as Inferred Mineral Resources due to the historical nature of the database. A bulk sampling programme would have to be undertaken to confirm the Mineral Resource in order for them to be converted to an Indicated Mineral Resource.</p>
	Whether the result appropriately reflects the Competent Person's view of the deposit.	It is the Competent Person's opinion the Mineral Resource estimation conducted by Minxcon is appropriate and presents a reasonable result in line with accepted industrial practices.
Audits or reviews	The results of any audits or reviews of Mineral Resource estimates.	Minxcon, as well as the Competent Person, conducted internal reviews of the Mineral Resource estimate, geological modelling and the data transformations from 2D to 3D.
Discussion of relative	Where appropriate a statement	Upon completion of the estimations, the older block models were visually checked with regards to the drillholes and sample points to the estimated values. Swath plot analysis was carried out on the newly estimated block models, comparing the chip samples and drillholes in a particular swath to the estimation block model also

accuracy/ confidence	of the relative accuracy and confidence level in the Mineral Resource estimate using an approach or procedure deemed appropriate by the Competent Person. For example, the application of statistical or geostatistical procedures to quantify the relative accuracy of the resource within stated confidence limits, or, if such an approach is not deemed appropriate, a qualitative discussion of the factors that could affect the relative accuracy and confidence of the estimate.	<p>falling within the same swath. The swath plots produce a good correlation with regards the estimation and the data in both the north-south plots and the east-west plots. The Competent Person deems the Mineral Resource estimate for the current estimated projects. The estimation conducted at the Theta Project underwent similar swath and visual checks as the historical Mineral Resource block model estimates.</p> <p>The Competent Person deems the Mineral Resource estimate for the Current Estimated Projects to reflect the relative accuracy relative to the Mineral Resource categories as required by the Code for the purposes of declaration and is of the opinion that the methodologies employed in the Mineral Resource estimation, based upon the data received may be considered appropriate.</p>
	The statement should specify whether it relates to global or local estimates, and, if local, state the relevant tonnages, which should be relevant to technical and economic evaluation. Documentation should include assumptions made and the	Regional accuracy is considered acceptable as evidenced by the swath plots, and direct sample point versus block model checks have ensured acceptable local accuracy with regards the estimated Projects.

	procedures used.	
	These statements of relative accuracy and confidence of the estimate should be compared with production data, where available.	Accuracy of the estimate relative to production data (historical projects) cannot be ascertained at this point as the project is still in the exploration phase. Accurate historical production figures are not readily available. At the Theta Project, a feasibility study has been completed with no accurate production data being available from the historical workings for the various reefs. Production has not commenced, thus "ground-truthing" at this point is not possible. Also, proposed open pit mining methods are not aligned to the historical underground mining methods employed.

SECTION 4: ESTIMATION AND REPORTING OF ORE RESERVES		
Criteria	Explanation	Detail
Mineral Resource estimate for conversion to Ore Reserves	Description of the Mineral Resource estimate used as a basis for the conversion to an Ore Reserve.	<p>Ore Reserves and mining were investigated for the Beta, Frankfort and CDM underground operations and the Theta Project (Theta Hill, Browns Hill and Iota Pit). The Ore Reserve estimation utilises the same Mineral Resource models used for the Mineral Resource classification.</p> <p>No Mineral Reserve cut-offs have been applied to the underground operations.</p> <p>The Theta Project conversion to Ore Reserves includes an Ore Reserve grade cut-off determined during the pit optimisation process with the relevant geological losses applied as part of the conversion factors.</p>
	Clear statement as to whether the Mineral Resources are reported additional to, or inclusive of, the Ore Reserves.	All Mineral Resources are stated as inclusive of the Ore Reserves.
Site visits	Comment on any site visits undertaken by the Competent Person and the outcome of those visits.	<p>The Competent Person Mr van Heerden has conducted a number of site visits of the gold properties held by TGM in the Sabie-Pilgrims Rest area since 2007. Mr van Heerden visited Project Area throughout 2019 to become familiar with project location and state of the land. From the site visits, an understanding of the potential layouts of the pits, infrastructure and infrastructure routes was formulated, as well as a general understanding of the practical design consideration. Further site visits were conducted on 7 March 2019 and 5 November 2019 with the purpose of introducing the potential mining contractors with the areas of interest, plant and pit areas, infrastructure build requirements and rock characteristics. On 22 September 2019, the Rietfontein Project was also visited with the purpose to identify access options for underground operations.</p>
	If no site visits have been undertaken indicate why this is the case.	Site visits have taken place, as described above.
Study status	The type and level of study undertaken to enable Mineral Resources to be converted to Ore Reserves.	<p>The Frankfort Mine is the only underground operation for which Measured Mineral Resources have been declared. The underground operations are at a Pre-Feasibility Level of Study and Measured Mineral Resources and Indicated Mineral Resources have been converted to Proved and Probable Ore Reserves respectively, using the appropriate modifying factors.</p> <p>No Measured Mineral Resources have been declared for the Theta Project. The Theta Project is at a Pre-Feasibility Study Level and Indicated Mineral Resources in the Theta Project have been converted to Probable Ore Reserves by having applied the required modifying factors.</p>
	The Code requires that a study to at least Prefeasibility Study level has been undertaken to convert Mineral Resources to Ore Reserves. Such studies will	Detailed LoM plans and schedules have been completed for the underground operations and the Theta Project. Some components are at a Feasibility Study Level with other components such as a geotechnical study at Pre-


SECTION 4: ESTIMATION AND REPORTING OF ORE RESERVES		
Criteria	Explanation	Detail
	have been carried out and will have determined a mine plan that is technically achievable and economically viable, and that material Modifying Factors have been considered.	<p>Feasibility Study Level. The studies conducted on the underground operations and Theta Project have been deemed at an overall PFS Level.</p> <p>Life of mine plans to a feasibility level of detail was the basis of the Ore Reserve classification. The mine plans take into consideration all relevant modifying factors and productivities. A financial valuation was conducted on the life of mine plans and was found economically viable.</p>
Cut-off parameters	The basis of the cut-off grade(s) or quality parameters applied.	<p>No cut-off was applied to the Beta, Frankfort and CDM Mines. A planning pay limit for each of the underground operations was calculated using current economic planning parameters. The planning pay limit was applied to the Mineral Resource model and blocks above the planning pay limit were included in the LoM designs. The planning pay limits applied to the underground operations are:</p> <ul style="list-style-type: none"> • Beta Mine: 170 cm.g/t; • Frankfort Mine: 163 cm.g/t; and • CDM Mine: 121 cm.g/t <p>The cut-off parameters was determined by completing a pit optimisation. The pit optimisation determines a range of economically viable pits from the pit optimisation inputs. A separate pit selection process followed where an economically viable pit shell was selected to be used as a template for mine design. The cut-off for the pit optimisation results determined in the optimisation software is 0.42 g/t.</p> <p>Understanding that all the tonnes in the pits will be mined an additional cut-off was calculated to determine the processing cut-off grade of 0.4 g/t which is applied as the Ore Reserve cut-off.</p>
Mining factors or assumptions	The method and assumptions used as reported in the Pre-Feasibility or Feasibility Study to convert the Mineral Resource to an Ore Reserve (i.e. either by application of appropriate factors by optimisation or by preliminary or detailed design).	<p>Only Measured and Indicated Mineral Resources have been converted to Proved and Probable Ore Reserves, respectively. No Inferred Mineral Resources have been included in the Ore Reserve estimation. The basis of the Ore Reserve estimation is detailed LoM designs and schedules for both the underground operations and the Theta Project.</p> <p>The Mineral Resource to Ore Reserve conversion requires application of appropriate factors which would account for any changes to the Mineral Resources in the life of mine plan as a result of mining the ore. As part of the technical studies the Ore Reserve conversion factors were determined and applied to the Mineral Resources in the LoM plan available for conversion to reserves.</p>
	The choice, nature and appropriateness of the selected mining method(s) and other mining parameters including associated design issues such as pre-strip, access, etc.	<p>The mining method selected to be implemented on the underground operations at Beta Mine, Frankfort Mine and CDM Mine, is mechanised long hole drilling applied to a narrow reef orebody. The mining method requires pre-development of a mining block in preparation for stoping operations. Rescue mining will be applied to the development ends allowing separate extraction of the reef and waste cuts. The selected mining method allows for minimal dilution.</p> <p>The mining method selected for the Theta is modified terrace mining and is suited to the mountainous profile of the current topography. The orebodies are considered stratified and on an inclined mountain. The steeply dipping nature of the mountain and relatively small scale of the operation eliminated the use of draglines and conventional strip mining. To overcome the steeply dipping orientation, the ore will be extracted on a flat surface whereby all the ore are extracted on the horizontal plane via ripping, loading and hauling.</p>
	The assumptions made regarding geotechnical parameters (e.g. pit slopes, stope sizes, etc.), grade control and pre-production drilling.	<p>Geotechnical studies for the Frankfort and Beta Mines have been completed at a PFS level. The recommendations as per the geotechnical reports have been applied to the Mineral Resources in the LoM plan to account for Pillar Losses. No geotechnical studies for the CDM Mine has been conducted and a Pillar Loss of 10% which is similar to the Beta and Frankfort operations have been applied.</p> <p>A combined overall slope angle of 40° was selected to accommodate all the rock type in the Theta Project. The selected slope angle is well in the range of the recommended slope angles.</p>
	The major assumptions made and Mineral Resource model used for pit and stope optimisation (if appropriate).	Geological Losses applied to the underground operations are 0 % for Measured Mineral Resources, 5 % for Indicated Mineral Resources and 10 % for Inferred Mineral Resources.

SECTION 4: ESTIMATION AND REPORTING OF ORE RESERVES																																																										
Criteria	Explanation	Detail																																																								
		Geological Losses applied to the Theta Project are 5% for the Indicated Mineral Resources, and 10% for the Inferred Mineral Resources.																																																								
		The Ore Reserve conversion factors applied to the underground operations are detailed in the table below.																																																								
		Ore Reserve Conversion Factors Applied to Underground Operations																																																								
		<table><tr><th>Area</th><th>Mining Factors</th><th>Unit</th><th>Value</th></tr><tr><td rowspan="4">Underground Operations</td><td>Pillar Loss Beta and CDM</td><td>%</td><td>10</td></tr><tr><td>Pillar Loss Frankfort</td><td>%</td><td>11</td></tr><tr><td>Oreloss</td><td>%</td><td>0.5</td></tr><tr><td>Dilution</td><td>%</td><td>1</td></tr></table>	Area	Mining Factors	Unit	Value	Underground Operations	Pillar Loss Beta and CDM	%	10	Pillar Loss Frankfort	%	11	Oreloss	%	0.5	Dilution	%	1																																							
	Area	Mining Factors	Unit	Value																																																						
Underground Operations	Pillar Loss Beta and CDM	%	10																																																							
	Pillar Loss Frankfort	%	11																																																							
	Oreloss	%	0.5																																																							
	Dilution	%	1																																																							
	The pillar loss applied to the Frankfort Mine is higher than the pillar loss applied to the Beta and CDM operations. The pillar loss applied to the Frankfort Mine was derived from the geotechnical study conducted.																																																									
	The mining dilution factors used.	The dilution factors applied due to dilution and ore loss for the Theta Project open pits are illustrated in																																																								
		Ore Reserve Conversion Factors Applied to the Theta Project																																																								
		<table><tr><th rowspan="2">Orebody Descriptions</th><th>Avg. Reef Width</th><th>Ore Loss</th><th>Dilution</th></tr><tr><th>cm</th><th>%</th><th>%</th></tr><tr><td>Beta</td><td>100</td><td>10.00%</td><td>10.00%</td></tr><tr><td>Upper Theta</td><td>100</td><td>10.00%</td><td>10.00%</td></tr><tr><td>Lower Theta</td><td>100</td><td>10.00%</td><td>10.00%</td></tr><tr><td>Bevetts</td><td>229</td><td>4.37%</td><td>4.37%</td></tr><tr><td>Upper Theta</td><td>100</td><td>10.00%</td><td>10.00%</td></tr><tr><td>Lower Theta</td><td>100</td><td>10.00%</td><td>10.00%</td></tr><tr><td>Bevetts</td><td>184</td><td>5.43%</td><td>5.43%</td></tr><tr><td>Shales</td><td>206</td><td>5.43%</td><td>5.43%</td></tr><tr><td>Lower Theta</td><td>114</td><td>8.77%</td><td>8.77%</td></tr><tr><td>Bevetts</td><td>114</td><td>8.77%</td><td>8.77%</td></tr><tr><td>Upper Rho</td><td>361</td><td>2.77%</td><td>2.77%</td></tr><tr><td>Lower Rho</td><td>550</td><td>1.82%</td><td>1.82%</td></tr></table>	Orebody Descriptions	Avg. Reef Width	Ore Loss	Dilution	cm	%	%	Beta	100	10.00%	10.00%	Upper Theta	100	10.00%	10.00%	Lower Theta	100	10.00%	10.00%	Bevetts	229	4.37%	4.37%	Upper Theta	100	10.00%	10.00%	Lower Theta	100	10.00%	10.00%	Bevetts	184	5.43%	5.43%	Shales	206	5.43%	5.43%	Lower Theta	114	8.77%	8.77%	Bevetts	114	8.77%	8.77%	Upper Rho	361	2.77%	2.77%	Lower Rho	550	1.82%	1.82%	
Orebody Descriptions	Avg. Reef Width	Ore Loss		Dilution																																																						
	cm	%	%																																																							
Beta	100	10.00%	10.00%																																																							
Upper Theta	100	10.00%	10.00%																																																							
Lower Theta	100	10.00%	10.00%																																																							
Bevetts	229	4.37%	4.37%																																																							
Upper Theta	100	10.00%	10.00%																																																							
Lower Theta	100	10.00%	10.00%																																																							
Bevetts	184	5.43%	5.43%																																																							
Shales	206	5.43%	5.43%																																																							
Lower Theta	114	8.77%	8.77%																																																							
Bevetts	114	8.77%	8.77%																																																							
Upper Rho	361	2.77%	2.77%																																																							
Lower Rho	550	1.82%	1.82%																																																							
	The mining recovery factors used.	A MCF of 100% was applied to the Theta Project as the product accounted for and product called for will have the necessary measuring methods in place so that all the product will be accounted for in the Theta Project. A MCF of 85 % was applied to the underground operations which was derived from similar operations using a similar mining layout and mining method.																																																								
	Any minimum mining widths used.	A minimum mining width of 60 cm was applied in the design of the underground operations. A 10 cm hangingwall and 10 cm footwall dilution is included in the 60 cm mining width that will be used in the development end resue mining and stoping operations. No minimum mining widths was used in the design of the Theta Project as the ripping of the dozers can rip the minimum orebody widths.																																																								
	The manner in which Inferred Mineral Resources are utilised in mining studies and the sensitivity of the outcome to their inclusion.	The underground LoM designs and schedules of the Beta, Frankfort and CDM mines includes a portion of Inferred Mineral Resources. The Inferred Mineral Resources have been excluded from the Ore Reserve estimate and the economic analysis. The Inferred Mineral Resources in the LoM plan for the underground operations are: <ul style="list-style-type: none">Beta Mine: 3.83%;Frankfort Mine: 21.92%CDM Mine: 25.71% The Inferred Mineral Resources in the Theta Project contain 8.10% of the total 2,355 kt Mineral Resource which adds up to 191 kt. The Inferred Mineral Resources cannot be included as Ore Reserves and were excluded from the economic analysis.																																																								
	The infrastructure requirements of the selected mining methods.	Infrastructure for the selected mining method includes:- <ul style="list-style-type: none">Mining contractor site – Earth Moving Vehicle workshops, stores, offices, changing facilities, fuel storage facility, wash bay and contractor's site power and water supply;Administrative and other offices and facilities;Underground trackless mining fleet and ancillary fleet;Haul roads;																																																								

SECTION 4: ESTIMATION AND REPORTING OF ORE RESERVES		
Criteria	Explanation	Detail
		<ul style="list-style-type: none"> • Waste rock dumps ("WRDs"); • Strategic ore stockpile; • RoM stockpile; • Topsoil stockpile; • Surface water management infrastructure – Dirty and clean water separation and storage and pit dewatering system. • Underground water management infrastructure – Dewatering system and water storage facilities. • Water supply and distribution infrastructure; • Power supply and distribution infrastructure; • Underground ore transport (Conveyor systems and Incline Winding Plant); • Surface ore load out and storage facilities; and • Low level river crossing.
Metallurgical factors or assumptions	The metallurgical process proposed and the appropriateness of that process to the style of mineralisation.	The OP-Plant will treat the free milling ore from the Theta Project with the conventional CIL process. Refractory Frankfort ore will be upgraded with DMS to reject some of the waste rock before the ore is trucked from the shaft to the plant. The UG-Plant will firstly remove the preg-robbler and then with Ultrafine Grinding to liberate the sulphide locked gold.
	Whether the metallurgical process is well-tested technology or novel in nature.	Most of the gold ore in the world are cyanide leached and adsorbed onto activated carbon is either a CIL or CIP configuration. DMS is frequently used to concentrate ores, including gold. Ultrafine grinding is widely used in gold and other commodities to extract metals from sulphides.
	The nature, amount and representativeness of metallurgical test work undertaken, the nature of the metallurgical domaining applied and the corresponding metallurgical recovery factors applied.	One grab sample was taken from the Beta mine and subjected to XRD and diagnostic leach. Four grab samples were taken from the available faces at the Frankfort mine and subjected to XRD and diagnostic leach by MSA. Following the poor recoveries achieved from the diagnostic leach the samples were sent for ultrafine grinding and then a bottle roll cyanide leach. No recent metallurgical testwork data was available for CDM. The daily production report from the old plant for May 2006 was used to estimate the recovery. Composite samples were made from RC Drilling chips to represent Upper Theta, Lower Theta and Beta. A master composite of these three was also tested. Tested done included diagnostic leach, kinetic leach and the effect of grind.
	Any assumptions or allowances made for deleterious elements.	The significant amounts of preg-robbles in the Frankfort ore will be removed by a flotation circuit. Additionally, the Frankfort ore will be treated in a intensive CIL which will further reduce the effect of the preg-robbler. A cyanide destruction circuit was included in the plant design which will ensure that the weak acid dissociable ("WAD") cyanide concentration in the tailings fraction that will be pumped to the TSF does not exceed the stipulated maximum level of 50 ppm.
	The existence of any bulk sample or pilot scale test work and the degree to which such samples are considered representative of the orebody as a whole.	No bulk sampling was completed.
	For minerals that are defined by a specification, has the ore reserve estimation been based on the appropriate mineralogy to meet the specifications?	Specifications are not applicable. The product will be sold as gold Doré to Rand Refinery with payability calculated based on the final gold content.
Environmental	The status of studies of potential environmental impacts of the mining and processing operation. Details of waste rock characterisation and the consideration of potential sites, status of design options considered and, where applicable, the status of approvals for process residue storage and waste dumps should be reported.	Owing to topography and the environmentally sensitive nature of the Theta Project Area a number of locations have been considered for the placement of WRDs for the open pit mining operation. The Theta Project Area has been sub-divided into two main areas. The first being the Browns Hill and Theta Hill area and the second the Iota area. Two WRD locations has been considered for each of these areas. All options have been designed in CAD mine design software and a preferred option chosen from a mining and engineering perspective. Waste rock from the TGM underground projects considered in the detailed studies will be placed on existing WRD's located at the CDM operation. Waste from the underground operations will be very limited as it will be placed in the stopping back areas and all development will be conducted on reef.

SECTION 4: ESTIMATION AND REPORTING OF ORE RESERVES		
Criteria	Explanation	Detail
		<p>Two options have been considered for the disposal of mine residue or tailings, and they will be used at the same time. There is an existing TSF that will be used for the initial deposition. This TSF will be brought up to the latest standards such as inclusion of an HDPE liner. Deposition on the TSF will be both hydraulic placement and dry stacking. The second disposal option is storage of tailings underground as a cemented paste backfill in the mined-out sections of the Beta Mine. Both these options will require relevant approvals which are still in progress.</p>
Infrastructure	The existence of appropriate infrastructure: availability of land for plant development, power, water, transportation (particularly for bulk commodities), labour, accommodation; or the ease with which the infrastructure can be provided, or accessed.	<p>The Theta Project Area is well established. Access roads are available and in a serviceable condition. The TGM underground projects considered in the detailed studies are historical project with established access roads leading to the individual project areas. Road require some minor repairs and upgrades in areas.</p> <p>Power supply to the Theta project is available on site and with some expansion / upgrades on the power supply system power supply capacity to the project will be sufficient. The TGM underground projects considered in the detailed studies does not currently grid power supply available. Power will be supplied to the CDM and Frankfort underground projects via diesel generators over their life of mine. The Beta underground project will initially be supplied with power from diesel generators and once the grid power supply in the area have been upgraded, grid power supply will be put in place for this project area.</p> <p>Based on a total project static water balance (includes – mine, processing plant and TSF) the project will be water positive during the wet season (October – March) and water negative during the dry months. Allowance has been made for the treatment of excess water as well as for a pumping system to supply any short falls of water. Additional make up water will be sourced from the Blyde River. Additional make up water sourced from the Blyde River is well within the allowable limits as stipulated in the existing water use licence (“WUL”).</p> <p>The TGM underground projects considered in the detailed studies will mainly be supplied with water from flooded underground workings and captured dirty rainwater. Provision have been made for boreholes that could supplement the water supply system if required. Potable water to the underground projects will be supplied from trucking of potable water from the town of Pilgrims Rest. Water available to the project is deemed to be sufficient.</p> <p>Gold from the TGM projects considered in the detailed studies, will be transported from site to Rand Refineries via helicopter. Allowance has been made for the construction of a Helistop on site for this purpose. Well established roads are in place in the project areas that allows for easy access and transport of material and equipment to and from the projects.</p> <p>The TGM projects considered in the detailed studies are located in an area of Mpumalanga which has long been associated with mining. Skilled labour can be sourced from nearby towns such as Lydenburg, Nelspruit and Steelpoort.</p> <p>Towns such as Lydenburg, Graskop and Sabie are well developed with facilities such as hospitals, police stations, schools and churches. These towns are located within 57 km of the Theta project and can thus provide accommodation to employees of the project.</p>
Costs	The derivation of, or assumptions made, regarding projected capital costs in the study.	Capital costs were estimated from first principles and engineering designs. Bills of quantities were utilised to obtain quotations for the capital cost estimation. The project capital has a base date of February 2021 and an exchange rate of ZAR/USD 15.06 were utilised where applicable to convert to USD terms.
	The methodology used to estimate operating costs.	<p>The mining and central services operating costs for the underground operations were derived from first principles cost estimations with some factoring.</p> <p>The mining operating costs for the open pit operations are sourced from budget quotes received from reputable contractors. The open pit central services cost was estimated from first principles and provided by TGM.</p>

SECTION 4: ESTIMATION AND REPORTING OF ORE RESERVES		
Criteria	Explanation	Detail
		<p>The plant operating costs were completed from first principles with consumable supplier quotes utilised were necessary.</p> <p>The corporate overheads were provided by TGM.</p> <p>Environmental and Social costs were calculated using the quatums provided by the Client as part of the Environmental Authorisation process.</p>
	Allowances made for the content of deleterious elements.	Allowance has been made for the costs associated with removal of deleterious elements (WAD cyanide) prior to deposition onto the TSF.
	The derivation of assumptions made of metal or commodity price(s), for the principal minerals and co-products.	The price forecasts are based on forecasts from Consensus Economics which considers various brokers and analyst forecasts; the long-term price was derived using an in-house model based on the real historic price trends.
	The source of exchange rates used in the study.	The exchange rate forecasts are based on forecasts sourced from various South African banks (ABSA, Investec, First National Bank and Nedbank) with the long-term exchange rate calculated using an in-house model based on the historic purchasing price parity of the Rand to the Dollar.
	Derivation of transportation charges.	Transport costs are based on indicative rates sourced from Rand Refinery; a conservative estimate has been used.
	The basis for forecasting or source of treatment and refining charges, penalties for failure to meet specification, etc.	Gold specification, refining charges and penalties are as per refining offer from Rand Refinery.
	The allowances made for royalties payable, both Government and private.	The refined Mineral and Petroleum Resources Royalty Act formula was used for this Project.
Revenue factors	The derivation of, or assumptions made regarding revenue factors including head grade, metal or commodity price(s) exchange rates, transportation and treatment charges, penalties, net smelter returns, etc.	The head-grade is based on an Ore Reserve LoM plan. The price forecasts are based on forecasts from Consensus Economics which considers various brokers and analyst forecasts; the long-term price was derived using an in-house model based on the real historic price trends. The exchange rate forecasts are based on forecasts sourced from various South African banks (ABSA, Investec, First National Bank and Nedbank) with the long-term exchange rate calculated using an in-house model based on the historic purchasing price parity of the Rand to the Dollar. Transport costs based on indicative rates sourced from Rand Refinery, conservative estimate used. Gold specification, refining charges, penalties and payabilities as per refining offer from Rand Refinery.
	The derivation of assumptions made of metal or commodity price(s), for the principal metals, minerals and co-products.	No co-products.
Market assessment	The demand, supply and stock situation for the particular commodity, consumption trends and factors likely to affect supply and demand into the future.	<ul style="list-style-type: none"> Gold demand fell by 10% year-on-year ("y-o-y") in the first three quarters of 2020 compared to 2019 primarily due to a slump in consumer demand as the world continues to fight the Covid-19 pandemic. Global central bank reserves grew by 247 t (-53% y-o-y), with Q3 seeing net sales for the first time since 2010. Total gold supply declined by 5% to y-o-y in the first three quarters of 2020 to 3,394 t primarily attributed to Covid-19 restrictions hampering both mining and recycling production. The gold price averaged USD1,770/oz in 2020, and in August 2020 broke the USD2,000/oz barrier for the first time. The gold price ended the year at USD1,883/oz. The elevated pricing was driven largely by global uncertainty and investors looking for safe-haven assets. <p>The global economy has been hit hard by the COVID-19 pandemic, with the IMF having projected a 4.9% contraction in global growth in 2020. Economic recovery is also unlikely to be swift, with a U-shaped recovery or even W-shaped recovery due to recurring waves of infection being the most realistic outcome (World Gold Council, 2020). The high levels of uncertainty coupled with long-lasting impact to investor portfolio performance make gold an attractive asset.</p>

SECTION 4: ESTIMATION AND REPORTING OF ORE RESERVES		
Criteria	Explanation	Detail
	A customer and competitor analysis along with the identification of likely market windows for the product.	 <p>Note: Various operations are inclusive of waste rock dumps mining or tailings retreatment operations which could</p> <p>Gold doré will be produced for sale. In the case of the Theta Project, Rand Refinery shall refine the material and if requested - sell, on their behalf. When compared to South African gold miners, the TGM operations are in the lower quartile on an AISC basis with an AISC of USD905/oz and USD1,042/oz for the UG operations and OP operations, respectively (excluding initial capital).</p>
	Price and volume forecasts and the basis for these forecasts.	Volume forecasts based on reserve LoM plan. The price forecasts are based on forecasts from Consensus Economics which considers various brokers and analyst forecasts; the long-term price was derived using an in-house model based on the real historic price trends.
	For industrial minerals the customer specification, testing and acceptance requirements prior to a supply contract.	N/A
Economic	The inputs to the economic analysis to produce the net present value (NPV) in the study, the source and confidence of these economic inputs including estimated inflation, discount rate, etc.	<p>In generating the financial model and deriving the valuations, the following were considered:-</p> <ul style="list-style-type: none"> This Report details the optimised cash flow model with economic input parameters. The cash flow model is in real money terms and completed in ZAR. The DCF valuation was set up in months starting April 2021, but also subsequently converted to calendar years. The annual ZAR cash flow was converted to USD using real term forecast exchange rates (Median of bank forecasts) to provide real results in this currency. A company hurdle rate of 5.0% (in real terms) was utilised for the discount factor. The impact of the Mineral Royalties Act using the formula for refined metals was included. Sensitivity analyses were performed to ascertain the impact of discount factors, commodity prices, exchange rate, grade, operating costs and capital expenditures. Valuation of the tax entity was performed on a stand-alone basis. The full NPV of the operation was reported for the Theta Project. No Inferred Mineral Resources was considered for the economic analysis.
	NPV ranges and sensitivity to variations in the significant assumptions and inputs.	

SECTION 4: ESTIMATION AND REPORTING OF ORE RESERVES																																			
Criteria	Explanation	Detail																																	
		<div style="display: flex; justify-content: space-around;"> <div> <p>UG Operations</p> </div> <div> <p>OP Operations</p> </div> </div> <p>The Project is most sensitive to the gold price, exchange rate, and grade, followed by mining and plant operating costs. The project is least sensitive to capital and other operating costs.</p> <table border="1"> <thead> <tr> <th>Real Discount Rate</th><th>Unit</th><th>UG Operations</th><th>OP Operations</th></tr> </thead> <tbody> <tr> <td>NPV @ 0%</td><td>USDm</td><td>122.9</td><td>34.1</td></tr> <tr> <td>NPV @ 2.5%</td><td>USDm</td><td>105.7</td><td>27.4</td></tr> <tr> <td>NPV @ 5%</td><td>USDm</td><td>91.2</td><td>21.9</td></tr> <tr> <td>NPV @ 7.5%</td><td>USDm</td><td>79.0</td><td>17.4</td></tr> <tr> <td>NPV @ 10%</td><td>USDm</td><td>67.6</td><td>13.4</td></tr> <tr> <td>NPV @ 12.5%</td><td>USDm</td><td>59.7</td><td>10.7</td></tr> <tr> <td>NPV @ 15%</td><td>USDm</td><td>52.1</td><td>8.2</td></tr> </tbody> </table>		Real Discount Rate	Unit	UG Operations	OP Operations	NPV @ 0%	USDm	122.9	34.1	NPV @ 2.5%	USDm	105.7	27.4	NPV @ 5%	USDm	91.2	21.9	NPV @ 7.5%	USDm	79.0	17.4	NPV @ 10%	USDm	67.6	13.4	NPV @ 12.5%	USDm	59.7	10.7	NPV @ 15%	USDm	52.1	8.2
Real Discount Rate	Unit	UG Operations	OP Operations																																
NPV @ 0%	USDm	122.9	34.1																																
NPV @ 2.5%	USDm	105.7	27.4																																
NPV @ 5%	USDm	91.2	21.9																																
NPV @ 7.5%	USDm	79.0	17.4																																
NPV @ 10%	USDm	67.6	13.4																																
NPV @ 12.5%	USDm	59.7	10.7																																
NPV @ 15%	USDm	52.1	8.2																																
Social	The status of agreements with key stakeholders and matters leading to social licence to operate.	<p>A public participation process has taken place as part of the 83MR Section 102 amendment process for inclusion of the Theta Project to establish community views and potential project impacts and incorporate social upliftment measures into the social strategy. Social engagement is ongoing until such time as the EA has been approved. A revised SLP has been submitted.</p> <p>It is noted that as at the effective date, illegal mining operations are active at the CDM site. This may delay CDM project commencement and appropriate arrangement for the removal of these illegal miners should be initiated.</p>																																	
Other	To the extent relevant, the impact of the following on the project and/or on the estimation and classification of the Ore Reserves:	-																																	
	Any identified material naturally occurring risks.	No material naturally occurring risks have been identified.																																	
	The status of material legal agreements and marketing arrangements.	There are no legal or marketing agreements in place for the Project.																																	
	The status of governmental agreements and approvals critical to the viability of the project, such as mineral tenement status, and government and statutory approvals. There must be reasonable grounds to expect that all necessary Government approvals will be received within the timeframes anticipated in the Pre-Feasibility or Feasibility study. Highlight and discuss the materiality of any unresolved matter that is dependent on a third party on which extraction of the reserve is contingent.	<p>Commissioning of the Project can only commence once all permits and authorisations have been approved. A Section 102 amendment application has been submitted to the DMRE for the addition of the Theta Project. Currently, a WULA process is underway to authorise the anticipated water uses at the open pit project. An EA process is also underway.</p>																																	
Classification	The basis for the classification of the Ore Reserves into varying confidence categories.	The appropriate category of Ore Reserve is determined primarily by the relevant level of confidence in the Mineral Resource. The Mineral Resource estimate, which includes all the project areas for TGM, was the basis of the																																	

SECTION 4: ESTIMATION AND REPORTING OF ORE RESERVES		
Criteria	Explanation	Detail
		Ore Reserve estimation for the Theta Project. The level of confidence in the Indicated Mineral Resource is sufficient to convert to Probable Ore Reserves.
	Whether the result appropriately reflects the Competent Person's view of the deposit.	The results as presented appropriately reflect the CP's view of the deposit.
	The proportion of Probable Ore Reserves that have been derived from Measured Mineral Resources (if any).	No Measured Mineral Resources was converted to Probable Ore Reserves.
Audits or reviews	The results of any audits or reviews of Ore Reserve estimates.	No external audits or reviews of the Theta Project Ore Reserves have been conducted.
Discussion of relative accuracy/ confidence	Where appropriate a statement of the relative accuracy and confidence level in the Ore Reserve estimate using an approach or procedure deemed appropriate by the Competent Person. For example, the application of statistical or geostatistical procedures to quantify the relative accuracy of the reserve within stated confidence limits, or, if such an approach is not deemed appropriate, a qualitative discussion of the factors which could affect the relative accuracy and confidence of the estimate.	The appropriate category of Ore Reserve is determined primarily by the relevant level of confidence in the Mineral Resource. The global Mineral Resource estimate, which includes all the project areas for TGM, was the basis of the local Ore Reserve estimation for the Theta Project. The level of confidence in the Indicated Mineral Resource is sufficient to convert to Probable Ore Reserves.
	The statement should specify whether it relates to global or local estimates, and, if local, state the relevant tonnages, which should be relevant to technical and economic evaluation. Documentation should include assumptions made and the procedures used.	The global Mineral Resource estimate, which includes all the project areas for TGM, was the basis of the local Ore Reserve estimation for the Theta Project.
	Accuracy and confidence discussions should extend to specific discussions of any applied Modifying Factors that may have a material impact on Ore Reserve viability, or for which there are remaining areas of uncertainty at the current study stage.	<p>The modifying factors applied were determined by technical studies at the appropriate level of confidence producing a mine plan and production schedule that is technically achievable and economically viable.</p> <p>The overall slope angles was determined with limited geotechnical information and requires additional technical work before project execution. A conservative approach was followed with the selection of the slope angles and any changes will have a minimal impact on the overall project.</p>
	It is recognised that this may not be possible or appropriate in all circumstances. These statements of relative accuracy and confidence of the estimate should be compared with production data, where available.	No previous Ore Reserve statements are available. However, the modifying factors were determined by technical studies and based on current operations utilising the selected mining method and are at the appropriate level of confidence to produce a mine plan and production schedule that is technically achievable and economically viable.